



BRUHAT BANGALORE MAHANAGARA PALIKE
BYATARAYANAPURA DIVISION

Name of Work: Package No.02 (Package consists of 14 works).

Name of the Agency: Benaka Developers & Project Pvt. Ltd.

MODIFIED ESTIMATE



TEJUS CONSULTANTS
CONSULTING ENGINEERS AND DESIGNERS

No.58 MIG, 6th Cross, 3rd Main

1st Stage, Basaveshwaranagar

Bangalore-560079

☎ 080 - 23287532

email: tejusconsultants@gmail.com

Bytarayanapura Division

Package No.02 (Package consists of 14 works).

Package No.02 (Package consists of 14 works).
Name Of work : - Package No.02 (Package consists of 14 works). Improvements to roads and drains OF Mandi MARIYAPPA Road via Mariyannapalya to Dasarahalli Main Road in Ward No.7,Byatarayanapura

Job Code :- 007-18-000109, 007-18-000110, 007-18-000111, 007-18-000112, 007-18-000113, 007-18-000114, 007-18-000115, 007-18-000116, 007-18-000117, 007-18-000118, 007-18-000119, 007-18-000120, 007-18-000121, 007-18-000122, 28873

Name of Agency :- M/S.Benaka Developers & Project Pvt.Ltd.

BOQ Item No	Modified Estimate												Rate Rs.	Amount Rs.
	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit			
	Chainage													
1	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWTD SR 2016-17)													
	Big Market Sahakarnagar 60ft													
	Sahakar Nagar 60ft Road (Big Market Road)													
	RHS													
	0.00	811.00		1	811.00			0.60	0.60	291.96				
	LHS													
	0.00	816.00		1	816.00			0.60	0.60	293.76				
	SAHAKARNAGAR 'A' BLOCK 15TH MAIN													
	RHS													
	0.00	203.00		1	203.00			0.60	0.45	54.81				
	LHS													
	0.00	203.00		1	203.00			0.60	0.45	54.81				
	SAHAKARNAGAR 3RD MAIN G Block													
	RHS													
	0.00	135.00		1	135.00			0.60	0.45	36.45				
	LHS													
	0.00	135.00		1	135.00			0.60	0.45	36.45				
	Big Market Sahakarnagar 60ft													
	Sahakaranagar													
	15th Main Road													
	0.00	77.50		1	77.50			0.60	0.50	23.25				
	15th Cross Road													
	0.00	217.50		1	217.50			0.60	0.50	65.25				
	16th Cross Road													
	0.00	193.20		1	193.20			0.60	0.50	57.96				
	16th main Road													
	0.00	214.50		1	214.50			0.60	0.50	64.35				
	17th Main Road													
	0.00	198.00		1	198.00			0.60	0.50	59.40				
	18th Main Road													
	0.00	151.10		1	151.10			0.60	0.50	45.33				
	18th Cross Road													
	0.00	137.60		1	137.60			0.60	0.50	41.28				
	19th main Road													
	0.00	148.00		1	148.00			0.60	0.50	44.40				
	19th Cross Road													
	0.00	110.00		1	110.00			0.60	0.50	33.00				
	19th A Cross Road													
	0.00	94.70		1	94.70			0.60	0.50	28.41				
	20th main Road													
	0.00	78.50		1	78.50			0.60	0.50	23.55				
	Happy Childhood Road													
	0.00	86.00		1	86.00			0.60	0.50	25.80				
	21st Main Road													

Amount	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
Rs.		Chainage										Rs.	Rs.
		Culvert		1	3.80			2.00	0.69	5.24			
		Culvert		1	5.00			2.00	0.69	6.90			
		Culvert		1	3.80			2.00	0.69	5.24			
		Amruth Nagar Sector A											
		Desilt											
		Amruthanagara A sector											
		1st Main Road											
		LHS											
		0.00 452.70		1	452.70			0.60	0.60	162.97			
		RHS											
		0.00 452.70		1	452.70			0.60	0.60	162.97			
		2nd Main Road in 1st Cross Raod											
		0.00 100.60		1	100.60			0.60	0.55	33.20			
		1st Cross Raod Block B Appartment											
		0.00 19.30		1.00	19.30			0.60	0.55	6.37			
		Sri Sai Sannidi Appartment Road Amruthnagar											
		Road B/W 1st cr & 2nd Cross rd											
		0.00 42.00		1	42.00			0.60	0.55	13.86			
		Road B/W 2nd Cross & 3rd Cross rd											
		0.00 31.00		1	31.00			0.60	0.55	10.23			
		Road B/W 3rd Cross & 4th Cross rd											
		0.00 30.80		1	30.80			0.60	0.55	10.16			
		Road B/W 4th Cross & 5th Cross											
		0.00 27.00		1.00	27.00			0.60	0.55	8.91			
		2nd Cross Road											
		0.00 157.60		1	157.60			0.60	0.55	52.01			
		3rd Cross Road											
		0.00 114.60		1	114.60			0.60	0.55	37.82			
		4th Cross Road											
		0.00 173.30		1	173.30			0.60	0.55	57.19			
		5th Cross Road											
		0.00 130.00		1	130.00			0.60	0.55	42.90			
		2nd B Cross Road											
		LHS											
		0.00 87.60		1	87.60			0.60	0.55	28.91			
		RHS											
		0.00 87.60		1	87.60			0.60	0.55	28.91			
		1st Main Road Beside BBMP Park											
		LHS											
		0.00 90.00		1	90.00			0.60	0.60	32.40			
		RHS											
		0.00 90.00		1	90.00			0.60	0.60	32.40			
		2nd Main Road											
		0.00 90.00		1	90.00			0.60	0.60	32.40			
		8th Cross Road											
		LHS											
		0.00 86.00		1	86.00			0.60	0.60	30.96			
		RHS											
		0.00 86.00		1	86.00			0.60	0.60	30.96			
		8th A Cross Road											
		LHS											
		0.00 38.20		1	38.20			0.60	0.60	13.75			
		New Drain											
		Appartment Beside Road (RHS)											
		0.00 85.00		1	85.00			0.70	0.15	8.93			
		Appartment Beside Road (LHS)											
		RHS											
		0.00 225.70		1	202.60			0.75	0.57	86.89			
		LHS											
		104.60 219.70		1	104.60			0.75	0.60	47.07			
		Maruthi Farm 5th cross Rd											
		RHS											
		0.00 50.60		1	50.60			0.75	0.60	22.77			
		LHS											
		0.00 87.10		1	87.10			0.70	0.60	36.58			
		2nd cross Rd											
		RHS											

Modified Estimate

Modified Estimate													
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	0.00	42.00		1	42.00			0.75	0.60	18.90			
	Culverts												
	Appartment Beside Road (LHS)												
	199.50	204.40	R/S	1	4.90			2.00	0.45	4.41			
	169.30	174.90	L/S	1	5.60			2.00	0.69	7.73			
	219.70	225.70	L/S	1	6.00			2.00	0.45	5.40			
	Across the Road												
	225.70	227.50		1	6.60			2.00	0.69	9.11			
	Amruth Nagar Sector A												
	Desilt												
	3rd Main Road												
	Amruthahalli Police Station Back Side												
	LHS												
	0.00	390.00		1	390.00			0.50	0.50	97.50			
	RHS												
	0.00	413.00		1	413.00			0.50	0.50	103.25			
	Over Burdan Earth												
				1	30.00			1.00	0.75	22.50			
				1	20.00			1.50	1.00	30.00			
				1	15.00			1.00	0.85	12.75			
				1	8.00			0.80	1.20	7.69			
	Pampa Extension Road												
	Desilt												
	Pampa Extension												
	1st Cross Road												
	0.00	39.90		1	39.90			0.60	0.55	13.17			
	2nd Cross Road												
	0.00	29.80		1	29.80			0.60	0.55	9.83			
	3rd Cross Road												
	0.00	24.10		1	24.10			0.60	0.55	7.95			
	4th Cross Road												
	0.00	66.00		1	66.00			0.60	0.55	21.78			
	9th Cross Road												
	0.00	92.70		1	92.70			0.60	0.55	30.59			
	11th Cross Road												
	0.00	69.50		1	69.50			0.60	0.55	22.94			
	12th Cross Road												
	0.00	126.10		1	126.10			0.60	0.55	41.61			
	2nd Main Road												
	0.00	68.60		1	68.60			0.60	0.55	22.64			
	3rd Main Road												
	0.00	138.80		1	138.80			0.60	0.55	45.80			
	4th Main Road												
	0.00	236.70		1	236.70			0.60	0.55	78.11			
	5th Main Road												
	0.00	241.10		1	241.10			0.60	0.55	79.56			
	Pampa Extension Road												
	Vinayaka Layout												
	1st Main Road												
	LHS												
	0.00	163.50		1	163.50			0.60	0.50	49.05			
	RHS												
	0.00	163.50		1	163.50			0.60	0.50	49.05			
	1st B Cross Road												
	LHS												
	0.00	64.40		1	64.40			0.60	0.50	19.32			
	RHS												
	0.00	64.40		1	64.40			0.60	0.50	19.32			
	2nd B Cross Road												
	LHS												
	0.00	81.00		1	81.00			0.60	0.50	24.30			
	RHS												
	0.00	81.00		1	81.00			0.60	0.50	24.30			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	Chainage											
	3rd Cross Road											
	LHS											
	0.00 76.60		1	76.60			0.60	0.50	22.98			
	RHS											
	0.00 76.60		1	76.60			0.60	0.50	22.98			
	4th A Cross Road											
	LHS											
	0.00 73.00		1	73.00			0.60	0.50	21.90			
	RHS											
	0.00 73.00		1	73.00			0.60	0.50	21.90			
	5th Cross Road											
	LHS											
	0.00 47.50		1	47.50			0.60	0.50	14.25			
	RHS											
	0.00 47.50		1	47.50			0.60	0.50	14.25			
	6th Cross Road											
	LHS											
	0.00 49.30		1	49.30			0.60	0.50	14.79			
	RHS											
	0.00 49.30		1	49.30			0.60	0.50	14.79			
	Kempapura											
	1st Cross Road											
	LHS											
	0.00 39.00		1	39.00			0.60	0.50	11.70			
	RHS											
	0.00 39.00		1	39.00			0.60	0.50	11.70			
	2nd Cross Road											
	LHS											
	0.00 38.70		1	38.70			0.60	0.50	11.61			
	RHS											
	0.00 38.70		1	38.70			0.60	0.50	11.61			
	3rd Cross Road											
	LHS											
	0.00 37.80		1	37.80			0.60	0.50	11.34			
	RHS											
	0.00 37.80		1	37.80			0.60	0.50	11.34			
	4th Cross Road											
	LHS											
	0.00 35.90		1	35.90			0.60	0.50	10.77			
	RHS											
	0.00 35.90		1	35.90			0.60	0.50	10.77			
	kallappa Layout											
	Desilt											
	1st Cross Road											
	LHS											
	0.00 44.30		1	44.30			0.50	0.40	8.86			
	RHS											
	0.00 43.90		1	43.90			0.50	0.40	8.78			
	1st A Cross Road											
	LHS											
	0.00 64.00		1	64.00			0.50	0.40	12.80			
	2nd Cross Road											
	LHS											
	0.00 43.60		1	43.60			0.50	0.40	8.72			</

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
	Chainage											Rs.	Rs.	
	0.00	43.60		1	43.60			0.50	0.40	8.72				
	2nd A Cross Road													
	LHS													
	0.00	76.50		1	76.50			0.50	0.40	15.30				
	RHS													
	0.00	76.50		1	76.50			0.50	0.40	15.30				
	Coffee Board Layout													
	Desilt													
	5th Cross Road													
	0.00	199.30		2	199.30			0.60	0.55	131.54				
	6th Cross Road													
	0.00	39.80		2	39.80			0.60	0.55	26.27				
	7th Cross Road													
	0.00	50.00		2	50.00			0.60	0.55	33.00				
	8th Cross Road													
	0.00	165.00		2	165.00			0.60	0.55	108.90				
	Kuvempu road(raghvendra circle to coffee board layout main road)													
	0.00	670.20		2	670.20			0.60	0.60	482.54				
	Hoysala Layout													
	5th Cross Road													
	LHS													
	0.00	48.00		1	48.00			0.60	0.60	17.28				
	RHS													
	3.00	48.00		1	35.00			0.60	0.60	12.60				
	Bhuvaneshwari nagar													
	St Anthony Church Road													
	RHS													
	0.00	140.00		1	140.00			0.90	1.03	130.05				
	Sanjeevini nagar													
	Desilt													
	Holy Trinity Church Road													
				1	15.00			0.50	0.50	3.75				
				1	15.00			0.50	0.50	3.75				
				1	5.00			0.50	0.50	1.25				
				1	10.00			0.50	0.50	2.50				
	New Culvert			1	9.60			1.80	0.90	15.55				
	Jakkur Double Rd													
	Desilt													
	Jakkur Layout													
	6th A Cross Road													
	LHS													
	0.00	34.20		1	34.20			0.50	0.50	8.55				
	RHS													
	0.00	34.20		1	34.20			0.50	0.50	8.55				
	13th A Cross Road													
	LHS													
	0.00	78.00		1	73.80			0.50	0.50	18.45				
	RHS													
	0.00	74.00		1	68.60			0.50	0.50	17.15				
	14th A Cross Road													
	LHS													
	0.00	68.00		1	59.00			0.50	0.50	14.75				
	RHS													
	0.00	68.00		1	68.00			0.50	0.50	17.00				
	15th A Cross Road													

Rs.	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
		LHS											
	0.00	212.00		1	175.00			0.50	0.50	43.75			
		RHS											
	0.00	212.00		1	206.00			0.50	0.50	51.50			
		Talakaveri Badavane 8th Cross Road											
		LHS											
	0.00	144.70		1	116.70			0.50	0.50	29.18			
		RHS											
	0.00	140.00		1	140.00			0.50	0.50	35.00			
		16th A Cross Road											
		LHS											
	0.00	125.10		1	125.10			0.50	0.50	31.28			
		RHS											
	0.00	125.00		1	125.00			0.50	0.50	31.25			
		17th A Cross Road											
		LHS											
	0.00	27.50		1	27.50			0.50	0.50	6.88			
		RHS											
	0.00	27.50		1	27.50			0.50	0.50	6.88			
		18th A Cross Road											
		LHS											
	0.00	46.00		1	46.00			0.50	0.50	11.50			
		RHS											
	0.00	46.00		1	16.00			0.50	0.50	4.00			
		Approach Road											
		LHS											
	0.00	100.50		1	100.50			0.50	0.50	25.13			
		RHS											
	0.00	15.00	R/S	1	15.00			0.50	0.50	3.75			
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.75			
	30.00	45.00	R/S	1	15.00			0.50	0.50	3.75			
	45.00	60.00	R/S	1	15.00			0.50	0.50	3.75			
	60.00	75.00	R/S	0	15.00			0.50	0.50	0.00	No work		
	75.00	90.00	R/S	1	15.00			0.50	0.50	3.75			
	90.00	100.50	R/S	1	10.50			0.50	0.50	2.63			
		19th Cross Road											
		LHS											
	0.00	135.00		1	111.00			0.50	0.50	27.75			
		RHS											
	0.00	137.00		1	113.00			0.50	0.50	28.25			
		19th A Cross Road											
		LHS											
	0.00	75.00		1	75.00			0.50	0.50	18.75			
		RHS											
	0.00	84.00		1	84.00			0.50	0.50	21.00			
		kuvempu Rd											
		Desilt											
		Kuvempu Road Coffe Board Layout (Road)											
		LHS											
	0.00	256.00		1	256.00			0.50	0.50	64.00			
		RHS											
	0.00	256.00		1	256.00			0.50	0.50	64.00			
		Gopalappa to Cof Board											
		Desilt											
		St Antony Church Road											
		(From Coffe Board Layout Park End)											
		LHS											
	0.00	440.00		1	350.00			0.50	0.50	87.50			
		RHS											
	0.00	570.00		1	432.00			0.50	0.50	108.00			
		Mandi mariyappa rd											
		Desilt											
		Mandi Mariyappa Reddy Road											
		LHS											
	0.00	746.00		1	471.00			0.50	0.50	117.75			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	RHS												
	0.00	746.00		1	706.00			0.50	0.50	176.50			
	Desilt												
	GS Shivarudrappa Circle to Prestige Misty Waters Apartment												
	LHS												
	0.00	415.00	L/S	1	290.00			0.60	0.90	156.60			
	RHS												
	0.00	2.30	R/S	1	395.00			0.60	0.90	213.30			
								Total Quantity		6651.86	Cum	217.12	1444251.84
2	KSRRB M200-15.2. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry B. Rubble Stone maonry in cement mortar (P.No.137, I.No.18.27 of PW,P&I WTD SR 2016-17)												
								Item of Work Not Operated					
								Total Quantity	0.00	Cum	406.89	0.00	
3	KSRRB M200-14.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. ii) Dismantling brick/Tile work B. In cement mortar. MORTH Specification No. 202 (P.No.137, I.No.18.23 of PW,P&I WTD SR 2016-17)												
								Item of Work Not Operated					
								Total Quantity	0.00	Cum	401.67	0.00	
4	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. (P.No.137, I.No.18.18 of PW,P&I WTD SR 2016-17)												
								Item of Work Not Operated					
								Total Quantity	0.00	Cum	549.11	0.00	
5	Removing and Resetting of Footpath Slab with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work												
	Big Market Sahakarnagar 60ft												
	Sahakar Nagar 60ft Road (Big Market Road)												
	RHS												
	0.00	811.00		1	706.50			1.20		847.80			
	LHS												
	0.00	816.00		1	656.60			1.20		787.92			
	Big Market Sahakarnagar 60ft												
	15th Cross Road												
	LHS												
	34.00	133.00		1	94.00			1.20		112.80			
	RHS												
	44.00	152.00		1	42.00			1.20		50.40			
	16th Cross Road												
	LHS												
	0.00	170.00		1	100.00			1.20		120.00			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	0.00	43.60		1	43.60			0.60	0.50	13.08			
20th Main Road													
	0.00	85.50		1	85.50			0.60	0.50	25.65			
Cubic Apartment apprtment side													
	0.00	65.15	L/S	1	65.15			0.80	0.70	36.48			
1st Main Road													
LHS													
	0.00	177.00	L/S	1	177.00			0.80	0.70	99.12			
RHS													
	0.00	177.00	R/S	1	169.00			0.80	0.70	94.64			
Connecting Road From 1st Mn to 2nd Main Road													
LHS													
	0.00	26.40	L/S	1	26.40			0.80	0.70	14.78			
RHS													
	0.00	26.40	R/S	1	26.40			0.80	0.70	14.78			
2nd Main Road													
LHS													
	0.00	202.00	L/S	1	181.10			0.80	0.70	101.42			
RHS													
	0.00	167.90		1	167.90			0.80	0.70	94.02			
1st Cross Road													
LHS													
	0.00	46.30		1	46.30			0.70	0.60	19.45			
2nd Cross Road													
LHS													
	0.00	44.90		1	44.90			0.70	0.60	18.86			
RHS													
	0.00	44.90		1	44.90			0.70	0.60	18.86			
3rd Cross Road													
LHS													
	0.00	44.60		1	44.60			0.70	0.60	18.73			
RHS													
	0.00	44.60		1	44.60			0.70	0.60	18.73			
4th Cross Road													
RHS													
	0.00	44.00		1	44.00			0.70	0.60	18.48			
Culvert													
1st Main Road													
RHS													
	74.00	82.00	R/S	1	8.00			1.80	0.80	11.52			
Cubic Apartment													
Culverts													
2nd Main Road Across The Road													
	103.70	105.50		1.00	10.00			1.80	0.80	14.40			
2nd Main Road													
LHS													
	19.00	154.00		1	20.90			1.50	0.60	18.81			
Amruth Nagar Sector A													
Amruth Nagar Sector A													
Culverts													
Culvert													
				1	7.50			2.00	0.92	13.80			
Culvert													
				1	6.20			2.00	0.92	11.41			
Culvert													
				1	5.00			2.00	0.69	6.90			
Culvert													
				1	6.20			2.00	0.69	8.56			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	74.00	77.00	R/S	1	3.00		1.20		3.60			
	Jakkur Double road											
	Desilt											
	Jakkur Layout											
	13th A Cross Road											
	LHS											
	0.00	78.00		1	67.80		0.60		40.68			
	14th A Cross Road											
	LHS											
	0.00	8.00	L/S	1	8.00		1.20		9.60			
	58.00	68.00	L/S	1	10.00		0.60		6.01			
	RHS											
	0.00	68.00		1	27.00		0.78		21.00			
	15th A Cross Road											
	RHS											
	49.00	59.50	R/S	1	10.50		0.90		9.45			
	16th A Cross Road											
	LHS											
	66.00	74.00	L/S	1	8.00		0.75		6.00			
	RHS											
	20.00	109.00		1	46.00		0.75		34.50			
	19th Cross Road											
	LHS											
	73.00	135.00		1	62.00		0.90		55.80			
	RHS											
	107.00	137.00		1	30.00		1.25		37.50			
	19th A Cross Road											
	LHS											
	66.00	75.00	L/S	1	9.00		1.00		9.00			
	RHS											
	66.00	84.00	R/S	1	18.00		1.00		18.00			
	Kuvempu Road											
	B.S Cover Slab											
	Kuvempu Road Coffe Board Layout (Road)											
	RHS											
	32.00	258.00		1	43.00		1.30		56.10			
	GS Shivarudrappa Circle to Prestige Misty Waters Apartment											
	LHS											
	0.00	415.00	L/S	1	208.70		0.90		187.83			
	RHS											
	0.00	266.10	R/S	1	266.10		0.90		239.49			
	Total Quantity											
	BOQ											
	Upto 125%											
	4099.48											
	4099.48											
	Sqm											
	141.78											
	581223.89											
	Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3) (P.No.25, I.No.5.33 of PW, P&IWD SR 2016-17)											
	Pampa Extension Road											
	Pampa											
	1st Cross Road											
	0.00	39.90		1	31.90		1.80		57.42			
	2nd Cross Road											
	0.00	29.80		1.00	26.80		1.80		48.24			
	3rd Cross Road											
	0.00	24.10		1.00	19.10		1.80		34.38			
	4th Cross Road											
	0.00	66.00		1	59.00		1.80		106.20			
	9th Cross Road											
	0.00	92.70		1	83.70		1.80		150.66			
	11th Cross Road											
	0.00	69.50		1	53.50		1.80		96.30			
	12th Cross Road											

BOQ Item No	Description	Unit	Quantity	Rate	Amount
				0.00	
2nd M			0.00		
3rd M			0.00		
4th M			0.00		
5th M			0.00		
	Pamp				
	Vinay				
1st M	LHS		15.00		
	RHS		5.00		
1st B	LHS		50.00		
	RHS		15.00		
	2nd B				
	LHS		5.00		
			51.00		
	RHS		31.00		
			76.00		
	3rd C				
	LHS		0.00		
			5.00		
	RHS		0.00		
			50.00		
	4th A				
	LHS		0.00		
	RHS		25.00		
	5th C				
	LHS		0.00		
			38.00		
	RHS		0.00		
	6th C				
	LHS		0.00		
	RHS		0.00		
	Kemp				
1st C	LHS		5.00		
			30.00		

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	Chainage											
	0.00 126.10		1	106.10			1.80		190.98			
	2nd Main Road											
	0.00 68.60		1	58.60			1.80		105.48			
	3rd Main Road											
	0.00 138.80		1	126.30			1.80		227.34			
	4th Main Road											
	0.00 236.70		1	211.70			1.80		381.06			
	5th Main Road											
	0.00 241.10		1	216.10			1.80		388.98			
									893.52			
	Pampa Extension Road											
	Vinayaka Layout											
	1st Main Road											
	LHS											
	15.00 142.00		1	65.00				1.80	117.00			
	RHS											
	5.00 163.50		1	76.50				1.80	137.70			
	1st B Cross Road											
	LHS											
	50.00 64.40	L/S	1	14.40				1.80	25.92			
	RHS											
	15.00 30.00	R/S	1	15.00				1.80	27.00			
	2nd B Cross Road											
	LHS											
	5.00 15.00	L/S	1	10.00				1.80	18.00			
	51.00 66.00	L/S	1	15.00				1.80	27.00			
	RHS											
	31.00 46.00	R/S	1	15.00				1.80	27.00			
	76.00 81.00	R/S	1	5.00				1.80	9.00			
	3rd Cross Road											
	LHS											
	0.00 5.00	L/S	1	5.00				1.80	9.00			
	5.00 15.00	L/S	1	10.00				1.80	18.00			
	RHS											
	0.00 5.00	R/S	1	5.00				1.80	9.00			
	50.00 65.00	R/S	1	15.00				1.80	27.00			
	4th A Cross Road											
	LHS											
	0.00 5.00	L/S	1	5.00				1.80	9.00			
	RHS											
	26.50 52.00		1	25.50				1.80	45.90			
	5th Cross Road											
	LHS											
	0.00 10.00	L/S	1	10.00				1.80	18.00			
	38.00 47.50	L/S	1	9.50				1.80	17.10			
	RHS											
	0.00 47.50		1	47.50				1.80	85.50			
	6th Cross Road											
	LHS											
	0.00 49.30		1	34.30				1.80	61.74			
	RHS											
	0.00 49.30		1	24.30				1.80	43.74			
	Kempapura											
	1st Cross Road											
	LHS											
	5.00 10.00	L/S	1	5.00				1.80	9.00			
	30.00 39.00	L/S	1	9.00				1.80	16.20			

Modified Estimate															Page 12 of 4
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No	
	Chainage											Rs.	Rs.		
	RHS								1.80	36.00				B.S	
	0.00	20.00		1	20.00									3rd	
	2nd Cross Road													Am	
	LHS								1.80	18.00				LH	
	0.00	10.00		1	10.00									RH	
	3rd Cross Road													B.S	
	LHS								1.80	18.00				3rd	
	0.00	10.00		1	10.00									Am	
	RHS								1.80	32.04				LH	
	10.00	37.80		1	17.80									RH	
	4th Cross Road													K	
	LHS								1.80	25.20				2	
	0.00	14.00		1	14.00										
	RHS								1.80	9.00					
	0.00	5.00	R/S	1	5.00				1.80	10.62					
	30.00	35.90	R/S	1	5.90					906.66					
	Amruth nagar A Sector													2	
	1st Main Road														
	LHS														
	0.00	452.70		1	433.70			1.80		780.66					
	RHS														
	0.00	452.70		1	432.70			1.80		778.86					
	2nd Main Road in 1st Cross Road														
	0.00	100.60		1	91.60			1.80		164.88					
	1st Cross Road Block B Apartment														
	0.00	19.30		1.00	19.30			1.80		34.74					
	Sri Sai Sannidi Apartment Road Amruthnagar														
	Road B/W 1st cr & 2nd Cross rd														
	0.00	42.00		1	38.00			1.80		68.40					
	Road B/W 2nd Cross & 3rd Cross rd														
	0.00	31.00		1.00	28.00			1.80		50.40					
	Road B/W 3rd Cross & 4th Cross rd														
	0.00	30.80		1.00	28.80			1.80		51.84					
	Road B/W 4th Cross & 5th Cross														
	0.00	27.00		1.00	25.00			1.80		45.00					
	2nd Cross Road														
	0.00	157.60		1	149.60			1.80		269.28					
	3rd Cross Road														
	0.00	114.60		1	105.60			1.80		190.08					
	4th Cross Road														
	0.00	173.30		1	162.30			1.80		292.14					
	5th Cross Road														
	0.00	130.00		1	120.00			1.80		216.00					
	2nd B Cross Road														
	LHS														
	0.00	87.60		1	82.60			1.80		148.68					
	RHS														
	0.00	87.60		1	81.60			1.80		146.88					
	1st Main Road Beside BBMP Park														
	LHS														
	0.00	90.00		1	83.00			1.80		149.40					
	RHS														
	0.00	90.00		1	83.00			1.80		149.40					
	2nd Main Road														
	0.00	90.00		1	85.00			1.80		153.00					
	8th Cross Road														
	LHS														
	0.00	86.00		1	81.00			1.80		145.80					
	RHS														
	0.00	86.00		1	81.00			1.80		145.80					
	8th A Cross Road														
	LHS														
	0.00	38.20		1	32.20			1.80		57.96					
	Amruth nagar A Sector									1211.76					

ent

[illegible]

Modified Estimate

Page 14

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.	BOQ Item No	Description
	Chainage								14.40					Chainage
	LHS						1.80		9.00					14th A Cross
	27.50 43.20	L/S	1	8.00			1.80							LHS
	49.20 78.00	L/S	1	5.00										17.00
	RHS						1.80		7.20					RHS
	0.00 29.00	R/S	1	4.00										17.00
	14th A Cross Road													15th A Cr
	LHS						1.80		9.00					LHS
	0.00 8.00	L/S	1	5.00			1.80		9.00					36.00
	47.00 58.00	L/S	1	5.00										RHS
	RHS						1.80		9.00					11.80
	8.00 17.00	R/S	1	5.00			1.80		10.80					Talakaveri
	58.00 68.00	R/S	1	6.00										LHS
	15th A Cross Road													36.00
	LHS						1.80		34.20					RHS
	36.00 173.00		1	19.00										15.00
	RHS						1.80		12.60					16th A Cro
	123.00 132.00	R/S	1	7.00			1.80		7.20					LHS
	187.50 206.00	R/S	1	4.00										0.00
	Talakaveri Badavane 8th Cross Road													RHS
	LHS						1.80		9.00					0.00
	36.00 62.00	L/S	1	5.00			1.80		10.80					17th A Cr
	90.00 105.00	L/S	1	6.00										LHS
	RHS						1.80		10.80					0.00
	45.00 60.00	R/S	1	6.00			1.80		5.40					18th A Cr
	105.00 122.00	R/S	1	3.00										30.0
	16th A Cross Road													Approac
	LHS						1.80		12.60					LHS
	30.00 37.00	L/S	1	7.00			1.80		9.00					30.00
	109.00 120.00	L/S	1	5.00										RHS
	RHS						1.80		14.40					0.00
	15.00 109.00		1	8.00										19th Cro
	17th A Cross Road													RHS
	LHS						1.80		9.00					24.00
	15.00 27.50	L/S	1	5.00			1.80		9.00					19th A
	RHS						1.80		7.20					LHS
	0.00 15.00	R/S	1	4.00										0.00
	18th A Cross Road													RHS
	LHS						1.80		10.80					0.00
	30.00 46.00	L/S	1	6.00			1.80		7.20					Kuven
	RHS						1.80		7.20					B.S Co
	30.00 46.00	R/S	1	4.00										Kuven
	Approach Road													LHS
	LHS						1.80		7.20					0.00
	15.00 30.00	L/S	1	4.00			1.80		9.00					RHS
	75.00 90.00	L/S	1	5.00										0.00
	RHS						1.80		27.00					Gopa
	30.00 100.50		1	15.00										B.S D
	19th Cross Road													St An
	LHS						1.80		36.00					(From
	24.00 135.00		1	20.00										LHS
	RHS						1.80		34.20					280
	24.00 120.00		1	19.00										RHS
	19th A Cross Road													135
	LHS						1.80		9.00					B.S
	15.00 25.00	L/S	1	5.00			1.80		3.60					St A
	66.00 75.00	L/S	1	2.00										(Fro
	RHS						1.80		10.80					LHS
	30.00 45.00	R/S	1	6.00			1.80		7.20					9
	60.00 66.00	R/S	1	4.00										RHS
	B.S Cover Slab													15
	Jakkur Layout													Ma
	6th A Cross Road													B.S
	RHS						0.90		13.50					Ma
	0.00 23.50		1	15.00										LH
	13th A Cross Road													1
	LHS						0.90		5.40					
	43.20 49.20	L/S	1	6.00										
	RHS						0.90							
	0.00 74.00		1	68.60										
							0.90		61.74					

Page 14 of 102		Modified Estimate										Page 15 of 102	
Amount Rs.	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
		14th A Cross Road											
		LHS											
		17.00 58.00		1	41.00			0.90		36.90			
		RHS											
		17.00 58.00		1	41.00			0.90		36.90			
		15th A Cross Road											
		LHS											
		36.00 177.00		1	95.50			0.90		85.95			
		RHS											
		11.80 206.00		1	78.50			0.90		70.65			
		Talakaveri Badavane 8th Cross Road											
		LHS											
		36.00 144.70		1	50.70			0.90		45.63			
		RHS											
		15.00 140.00		1	111.00			0.90		99.90			
		16th A Cross Road											
		LHS											
		0.00 125.10		1	117.10			0.90		105.39			
		RHS											
		0.00 125.10		1	71.00			0.90		63.90			
		17th A Cross Road											
		LHS											
		0.00 27.50		1	27.50			0.90		24.75			
		18th A Cross Road											
		30.00 46.00	R/S	1	16.00			0.90		14.40			
		Approach Road											
		LHS											
		30.00 100.50		1	70.50			0.90		63.45			
		RHS											
		0.00 100.50		1	85.50			0.90		76.95			
		19th Cross Road											
		RHS											
		24.00 107.00		1	67.00			0.90		60.30			
		19th A Cross Road											
		LHS											
		0.00 48.00		1	48.00			0.90		43.20			
		RHS											
		0.00 66.00		1	66.00			0.90		59.40			
		Kuvempu Rd											
		B.S Cover Slab											
		Kuvempu Road Coffe Board Layout (Road)											
		LHS											
		0.00 215.00		1	208.00			0.93		192.42			
		RHS											
		0.00 258.00		1	209.00			0.93		193.50			
		Gopalappa to Cof Board											
		B.S Drain											
		St Antony Chaurch Road											
		(From Coffe Board Layout Park End)											
		LHS											
		280.00 400.00		1	12.00			1.80		21.60			
		RHS											
		135.00 420.00		1	31.00			1.80		55.80			
		B.S Cover Slab											
		St Antony Chaurch Road											
		(From Coffe Board Layout Park End)											
		LHS											
		90.00 570.00		1	81.00			0.90		72.90			
		RHS											
		150.00 570.00		1	85.00			0.90		76.50			
		Mandi mariyappa rd											
		B.S Drain											
		Mandi Mariyappa Reddy Road											
		LHS											
		180.00 705.00		1	32.00			1.80		57.60			

Modified Estimate													Page 18 of 18	
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.	BOQ Item No	Description
	Chainage													Chainage
	RHS		1	39.00			1.80		70.20					0.00
	90.00	630.00												125
	B.S Cover Slab													2nd Main Road
	Mandi Mariyappa Reddy Road													0.00
	LHS		1	132.00			0.90		118.80					68
	180.00	761.00												3rd Main Road
	RHS		1	75.00			0.90		67.50					0.00
	30.00	750.00												13
	GS Shivarudrappa Circle to Prestige Misty Waters Apartment													4th Main Road
		L/S	1	6.70			0.90		6.03					0.00
		R/S	1	40.60			0.90		36.54					23
														5th Main Road
														0.00
														24
														Pampa Extension
														Vinayaka Layout
														1st Main Road
														LHS
														75.00
														142.00
														RHS
														75.00
7	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWD SR 2016-17)													
	Cubic Apartment													
	apprtment side													
	0.00	65.15	1	65.15				1.80	117.27					1st B Cross
														LHS
	1st Main Road													45.00
	LHS		1	177.00				1.80	318.60					RHS
	0.00	177.00												0.00
	RHS		1	169.00				1.80	304.20					
	0.00	177.00												2nd B Cross
	Connecting Road From 1st Mn to 2nd Main Road													LHS
	LHS		1	26.40				1.80	47.52					30.00
	0.00	26.40	L/S											RHS
	RHS		1	26.40				1.80	47.52					9.00
	0.00	26.40	R/S											
	2nd Main Road													
	LHS		1	181.10				1.80	325.98					3rd Cross
	0.00	202.00												LHS
	RHS		1	167.90				1.80	302.22					42.00
	0.00	167.90												RHS
	1st Cross Road													42.00
	LHS		1	46.30				1.50	69.45					
	0.00	46.30												4th A Cro
	2nd Cross Road													LHS
	LHS		1	44.90				1.50	67.35					60.00
	0.00	44.90												RHS
	RHS		1	44.90				1.50	67.35					52.00
	0.00	44.90												
	3rd Cross Road													5th Cross
	LHS		1	44.60				1.50	66.90					LHS
	0.00	44.60												10.00
	RHS		1	44.60				1.50	66.90					
	0.00	44.60												6th Cro
	4th Cross Road													LHS
	RHS		1	44.00				1.50	66.00					15.00
	0.00	44.00												RHS
														5.00
	Pampa Extension Road													
	Pampa Extension													
	1st Cross Road		1	8.00				1.80	14.40					Kemp
	0.00	39.90												1st Cr
	2nd Cross Road		1.00	3.00				1.80	5.40					LHS
	0.00	29.80												0.00
	3rd Cross Road		1.00	5.00				1.80	9.00					20.00
	0.00	24.10												RHS
	4th Cross Road		1	7.00				1.80	12.60					20.00
	0.00	66.00												
	9th Cross Road		1	9.00				1.80	16.20					
	0.00	92.70												
	11th Cross Road		1	16.00				1.80	28.80					
	0.00	69.50												
	12th Cross Road							1.80						

Page No.	Amount	Ref.	SOQ Item No	Description	Chainage	0.00	128
				2nd Main Road	0.00	68	
				3rd Main Road	0.00	13	
				4th Main Road	0.00	23	
				5th Main Road	0.00	24	
				Pampa Extension			
				Vinayaka Layout			
				1st Main Road	LHS		
					75.00		
					142.00		
					RHS		
					75.00		
				1st B Cross	LHS		
					45.00		
					RHS		
					0.00		
				2nd B Cross	LHS		
					30.00		
					RHS		
					9.00		
				3rd Cross	LHS		
					42.00		
					RHS		
					42.00		
				4th A Cross	LHS		
					60.00		
					RHS		
					52.00		
				5th Cross	LHS		
					10.00		
				6th Cross	LHS		
					15.00		
					RHS		
					5.00		
				Kemp			
				1st Cross	LHS		
					0.00		
					20.00		
					RHS		
					20.00		

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	Chainage											
	0.00 126.10		1	20.00			1.80		36.00			
	2nd Main Road											
	0.00 68.60		1	10.00			1.80		18.00			
	3rd Main Road											
	0.00 138.80		1	12.50			1.80		22.50			
	4th Main Road											
	0.00 236.70		1	25.00			1.80		45.00			
	5th Main Road											
	0.00 241.10		1	25.00			1.80		45.00			
	Pampa Extension Road											
	Vinayaka Layout											
	1st Main Road											
	LHS											
	75.00 82.50	L/S	1	7.50				1.80	13.50			
	142.00 145.00	L/S	1	3.00				1.80	5.40			
	RHS											
	75.00 82.50	R/S	1	7.50				1.80	13.50			
	1st B Cross Road											
	LHS											
	45.00 50.00	L/S	1	5.00				1.80	9.00			
	RHS											
	0.00 5.00	R/S	1	5.00				1.80	9.00			
	2nd B Cross Road											
	LHS											
	30.00 33.00	L/S	1	3.00				1.80	5.40			
	RHS											
	9.00 18.00	R/S	1	9.00				1.80	16.20			
	3rd Cross Road											
	LHS											
	42.00 50.00	L/S	1	8.00				1.80	14.40			
	RHS											
	42.00 50.00	R/S	1	8.00				1.80	14.40			
	4th A Cross Road											
	LHS											
	60.00 73.00	L/S	1	13.00				1.80	23.40			
	RHS											
	52.00 73.00	R/S	1	15.00				1.80	27.00			
	5th Cross Road											
	LHS											
	10.00 25.00	L/S	1	15.00				1.80	27.00			
	6th Cross Road											
	LHS											
	15.00 30.00	L/S	1	15.00				1.80	27.00			
	RHS											
	5.00 15.00	R/S	1	10.00				1.80	18.00			
	Kempapura											
	1st Cross Road											
	LHS											
	0.00 5.00	L/S	1	5.00				1.80	9.00			
	20.00 30.00	L/S	1	10.00				1.80	18.00			
	RHS											
	20.00 32.00	R/S	1	12.00				1.80	21.60			

Modified Estimate

Modified Estimate														Rate	Amount
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rs.	Rs.	BOQ Item No	Description	
	Chainage														
	2nd Cross Road														
	RHS														
	0.00 5.00	R/S	1	5.00				1.80	9.00						
	30.00 38.70	R/S	1	8.70				1.80	15.66						
	3rd Cross Road														
	LHS														
	30.00 37.80	L/S	1	7.80				1.80	14.04						
	RHS														
	5.00 10.00	R/S	1	5.00				1.80	9.00						
	4th Cross Road														
	LHS														
	15.00 30.00	L/S	1	15.00				1.80	27.00						
	Amruth nagar A sector														
	New Drain														
	Appartment Beside Road (RHS)														
	0.00 85.00		1	85.00			1.20		102.00						
	Appartment Beside Road (LHS)														
	RHS														
	0.00 225.70		1	202.60			1.76		357.24						
	LHS														
	104.60 219.70		1	104.60			1.80		188.28						
	Maruthi Farm 5th cross Rd														
	RHS														
	0.00 50.60		1	50.60			1.80		91.08						
	LHS														
	0.00 87.10		1	87.10			1.80		156.78						
	2nd cross Rd														
	RHS														
	0.00 42.00		1	42.00			1.80		75.60						
	Amruth nagar A Sector														
	1st Main Road														
	LHS														
	0.00 452.70		1	19.00			1.80		34.20						
	RHS														
	0.00 452.70		1	20.00			1.80		36.00						
	2nd Main Road in 1st Cross Road														
	0.00 100.60		1	9.00			1.80		16.20						
	1st Cross Road Block B Appartment														
	0.00 19.30		1.00	0.00			1.80		0.00						
	Sri Sai Sannidi Appartment Road Amruthnagar														
	Road B/W 1st cr & 2nd Cross rd														
	0.00 42.00		1	4.00			1.80		7.20						
	Road B/W 2nd Cross & 3rd Cross rd														
	0.00 31.00		1.00	3.00			1.80		5.40						
	Road B/W 3rd Cross & 4th Cross rd														
	0.00 30.80		1.00	2.00			1.80		3.60						
	Road B/W 4th Cross & 5th Cross														
	0.00 27.00		1.00	2.00			1.80		3.60						
	2nd Cross Road														
	0.00 157.60		1	8.00			1.80		14.40						
	3rd Cross Road														
	0.00 114.60		1	9.00			1.80		16.20						
	4th Cross Road														
	0.00 173.30		1	11.00			1.80		19.80						
	5th Cross Road														
	0.00 130.00		1	10.00			1.80		18.00						
	2nd B Cross Road														
	LHS														
	0.00 87.60		1	5.00			1.80		9.00						
	RHS														
	0.00 87.60		1	6.00			1.80		10.80						
	1st Main Road Beside BBMP Park														
	LHS														
	0.00 90.00		1	7.00			1.80		12.60						
	RHS														

Rs.	ROQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
		0.00 90.00		1	7.00			1.80		12.60			
		2nd Main Road											
		0.00 90.00		1	5.00			1.80		9.00			
		8th Cross Road											
		LHS											
		0.00 86.00		1	5.00			1.80		9.00			
		RHS											
		0.00 86.00		1	5.00			1.80		9.00			
		8th A Cross Road											
		LHS											
		0.00 38.20		1	6.00			1.80		10.80			
		Amruth nagar A sector											
		B.S Drain											
		3rd Main Road											
		Amruthahalli Police Station Back Side											
		15.00 375.00		1	86.00			1.80		154.80			
		RHS											
		0.00 413.00		1	79.00			1.80		142.20			
		Kallappa Layout											
		1st A Cross Road											
		15.00 45.00		1	2.00			1.80		3.60			
		2nd Cross Road											
		LHS											
		0.00 30.00		1	2.00			1.80		3.60			
		RHS											
		0.00 30.00		1	2.00			1.80		3.60			
		2nd A Cross Road											
		LHS											
		0.00 30.00		1	2.00			1.80		3.60			
		RHS											
		0.00 15.00		1.00	1.00			1.80		1.80			
		2nd RA Coffee Board Layout											
		5th Cross Road											
		0.00 199.00		2	40.00			1.80		144.00			
		6th Cross Road											
		0.00 39.80		2	8.00			1.80		28.80			
		7th Cross Road											
		0.00 50.00		2	13.00			1.80		46.80			
		8th Cross Road											
		0.00 165.00		2	30.00			1.80		108.00			
		Sanjeevini nagar											
		B.S Cover Slab											
		Holy Trinity Chaurch Road											
		LHS											
		0.00 35.00	L/S	1	35.00			0.90		31.50			
		Jakkur Double Rd											
		B.S Drain											
		B.S Drain											
		Jakkur Layout											
		6th A Cross Road											
		LHS											
		0.00 25.00		1	8.00			1.80		14.40			
		RHS											
		0.00 31.00		1	10.00			1.80		18.00			
		13th A Cross Road											
		LHS											
		0.00 49.20		1	11.00			1.80		19.80			
		14th A Cross Road											
		LHS											
		17.00 47.00		1	11.00			1.80		19.80			
		RHS											
		17.00 32.00	R/S	1	8.00			1.80		14.40			
		15th A Cross Road											
		LHS											
		90.50 103.00	L/S	1	8.00			1.80		14.40			
		143.00 158.00	L/S	1	9.00			1.80		16.20			

[illegible]

Modified Estimate														Page 21 of 102	
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount		
	Chainage											Rs.	Rs.		
9	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS(P.No.6, I.No.2.15 of PW,P&I/WTDS.R 2016-17)														
	Item of Work Not Operated														
	Total Quantity									0.00	Cum	2442.94	0.00		
10	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.No.12, I.No.4.2 of PW,P&I/WTDS.R 2016-17)														
	Cubic Apartment														
	Culvert														
	1st Main Road														
	RHS														
	74.00	82.00	R/S	1	8.00			1.80	0.15	2.16					
	Cubic Apartment														
	Culverts														
	2nd Main Road Across The Road														
	103.70	105.50		1.00	10.00			1.80	0.15	2.70					
	2nd Main Road														
	LHS														
	19.00	25.50	L/S	1.00	6.50			1.50	0.15	1.46					
	87.00	91.00	L/S	1.00	4.00			1.50	0.15	0.90					
	118.00	123.00	L/S	1.00	5.00			1.50	0.15	1.13					
	148.60	154.00	L/S	1.00	5.40			1.50	0.15	1.22					
	Amruth Nagar Sector A														
	Amruth														
	Culverts														
	Culvert														
				1	7.50			2.00	0.15	2.25					
	Culvert														
				1	6.20			2.00	0.15	1.86					
	Culvert														
				1	5.00			2.00	0.15	1.50					
	Culvert														
				1	6.20			2.00	0.15	1.86					
	Culvert														
				1	3.80			2.00	0.15	1.14					
	Culvert														
				1	5.00			2.00	0.15	1.50					
	Culvert														
				1	3.80			2.00	0.15	1.14					
	Amruth Nagar Sector A														
	Culverts														
	Appartme														
	199.50	204.40		1	4.90			2.00	0.15	1.47					
	169.30	174.90		1	5.60			2.00	0.15	1.68					
	219.70	225.70		1	6.00			2.00	0.15	1.80					
	Across														
	225.70	227.50		1	6.60			2.00	0.15	1.98					
	Kallappa Layout														
	1st Cross Road														
	LHS														
	0.00	44.30		2	44.30			0.30	0.10	2.66					

Modified Estimate

[illegible]

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	0.00 90.00	R/S	4	90.00				0.75	270.00			
	90.00 140.00	R/S	4	50.00				0.70	140.00			
								Total Quar	410.00			
								Quantity Lim	172.80	Sqm	332.32	57,424.90
13	Providing and laying cement concrete using 20mm and downsize granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cpost of steel and fabrication charges). Ready Mixed Cement Concrete M 20 for Raft foundation, Column, Footing, main and secondary beams. (P.No.18, I.No.4.48 of PW, P&I WTD SR 2016-17)											
	Bhuvanehwari nagar											
	St Anthony Church Road											
	RHS											
	For Bottom Raft											
	0.00 140.00	R/S	1	140.00			0.90	0.15	18.90			
	Side Wall											
	0.00 90.00	R/S	2	90.00			0.15	0.75	20.25			
	90.00 140.00	R/S	2	50.00			0.15	0.70	10.50			
	Cast In Situ Slab											
			1	5.00			1.10	0.20	1.10			
									Total Quantity	50.75		
									Quantity Limited To	38.40	Cum	6667.96 2,56,049.66
14	KSRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebtrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (P.No.17, I.No.4.46.2 of PW, P&I WTD SR 2016-17)											
	Bhuvanehwari nagar											
	St Anthony Church Road											
	RHS											
	Main Bars											
	10 mm dia Bars		700.00	2.40			0.62		1037.04			
	Distribution Bars											
	8 mm Dia Bars		15.00	140.00			0.40		829.63			
	Cast In Situ Slab											
	Main Bars											
	10 mm dia Bars		25.00	1.10			0.62		16.98			
	Distribution Bars											
	8 mm Dia Bars		6.00	5.00			0.40		11.85			
									1895.49			
									Total Quantity	1.90	Tonne	68740.46 1,30,297.12
15	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 5.00 N/mm ² confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.12, I.No.5.27.2 of PW,P&I WTD S.R 2016-17)											
	Kallappa Layout											
	1st Cross Road											
	LHS											
	0.00 44.30		2	44.30				0.40	35.44			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	Amruth Nagar Sector A											
	Culverts											
	Appartme											
	199.50 204.40		2.00	4.90			0.45	0.45	1.98			
	169.30 174.90		2.00	5.60			0.45	0.69	3.48			
	219.70 225.70		2.00	6.00			0.45	0.45	2.43			
	Across											
	225.70 227.50		2.00	6.60			0.45	0.69	4.10			
	Sanjeevini nagar											
	New Culvert		2	9.60			0.60	0.60	6.91			
							Total		73.38	cum	4748.9	3,48,457.19
17	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.113, I.No.15.1 of PW, P&I WTD S.R 2016-17)											
	Cubic Apartment											
	Culvert											
	1st Main Road											
	RHS											
	74.00 82.00	R/S	2	8.00				0.69	11.04	culvert		
	Cubic Apartment											
	Culverts											
	2nd Main Road Across The Road											
	103.70 105.50		2.00	10.00				0.69	13.80			
	2nd Main Road											
	LHS											
	19.00 25.50	L/S	2.00	6.50				0.45	5.85			
	87.00 91.00	L/S	2.00	4.00				0.45	3.60			
	118.00 123.00	L/S	2.00	5.00				0.45	4.50			
	148.60 154.00	L/S	2.00	5.40				0.45	4.86			
	Amruth Nagar Sector A											
	Culverts											
	Culvert		2	7.50				0.92	13.80			
	Culvert		2	6.20				0.92	11.41			
	Culvert		2	5.00				0.69	6.90			
	Culvert		2	6.20				0.69	8.56			
	Culvert		2	3.80				0.69	5.24			
	Culvert		2	5.00				0.69	6.90			
	Culvert		2	3.80				0.69	5.24			
	Amruth Nagar Sector A											
	Culverts											
	Appartment Beside Road (LHS)											
	199.50 204.40		2.00	4.90				0.45	4.41			
	169.30 174.90		2.00	5.60				0.69	7.73			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	RHS											
	0.00 170.00		1	29.00			1.80		52.20			
	Talakaveri Badavane 8th Cross Road											
	LHS											
	75.00 90.00	L/S	1	5.00			1.80		9.00			
	135.00 143.50	L/S	1	5.00			1.80		9.00			
	RHS											
	0.00 140.00		1	25.00			1.80		45.00			
	16th A Cross Road											
	LHS											
	0.00 125.00		1	29.10			1.80		52.38			
	RHS											
	20.00 125.00		1	23.00			1.80		41.40			
	17th A Cross Road											
	LHS											
	0.00 15.00	L/S	1	6.00			1.80		10.80			
	RHS											
	15.00 27.50	R/S	1	3.00			1.80		5.40			
	18th A Cross Road											
	LHS											
	0.00 30.00		1	9.00			1.80		16.20			
	Approach Road											
	LHS											
	0.00 100.50		1	21.00			1.80		37.80			
	RHS											
	0.00 90.00		1	19.00			1.80		34.20			
	19th Cross Road											
	LHS											
	45.00 90.00		1	14.00			1.80		25.20			
	RHS											
	45.00 60.00	R/S	1	8.00			1.80		14.40			
	19th A Cross Road											
	LHS											
	0.00 66.00		1	10.00			1.80		18.00			
	RHS											
	0.00 84.00		1	18.00			1.80		32.40			
	Gopalappa to Cof board											
	B.S Drain											
	St Antony Church Road											
	(From Coffe Board Layout Park End)											
	LHS											
	0.00 440.00		1	120.00			1.80		216.00			
	RHS											
	0.00 570.00		1	166.00			1.80		298.80			
	Mandi Mariyappa rd											
	B.S Drain											
	Mandi Mariyappa Reddy Road											
	LHS											
	0.00 746.00		1	155.00			1.80		279.00			
	RHS											
	0.00 746.00		1	252.00			1.80		453.60			
	Total											
									6135.12	Sqm	712.28	43,69,926.54
8	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete. 10cms thick (P.No.25, I.No.5.31.2 of PW, P&I WTD SR 2016-17)											
	Item of Work Not Operated											
	Total Quantity											
									0.00	Sqm	883.54	0.00

Rs.	BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
		Coping Concrete											
		Holy Trinity Chaurch Road		1	35.00			0.15	0.10	0.53			
				1	35.00			0.15	0.10	0.53			
				2	10.00			0.15	0.10	0.30			
		New Culvert											
		Bottom Concrete		1	9.60			1.80	0.15	2.59			
		Coping Concrete		2	9.60			0.10	0.60	1.15			
		For Kerb Bottom											
		Aralemara side		1	105.00			0.20	0.10	2.10			
				1	12.00			0.20	0.10	0.24			
								Total		34.61	Cum	6171.18	2,13,609.22
	19	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, grinding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 109, I.No. 14.62 of PWD SR 2016-17)											
		Big Market Sahakarnagar 60ft											
		Sahakar Nagar 60ft Road (Big Market Road)											
		RHS											
		0.00	712.50	1	475.00	1.00	1.00	1.00		475.00			
		LHS											
		0.00	706.00	1	661.00	1.00	1.00	1.00		661.00			
								Total		1136.00	Sqm	1230.61	1397972.96
	20	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer-in-charge. (Data Rate) with all lead and lift , loading and unloading and aliother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work											
		Big Market Sahakarnagar 60ft											
		Sahakar Nagar 60ft Road (Big Market Road)											
		RHS											
		0.00	811.00	1	69.00			1.20		82.80			
		LHS											
		37.20	816.00	1	88.30			1.20		105.96			
		Kallappa Layout											
		1st Cross											
		LHS											
		0.00	44.30	1.00	44.30			0.90		39.87			
		RHS											
		0.00	43.90	1.00	41.50			0.90		37.35			
		1st A											
		LHS											
		0.00	15.00	1.00	58.50			0.90		52.65			
		2nd											
		LHS											
		0.00	43.60	1.00	20.10			0.90		18.09			
		RHS											
		0.00	43.60	1.00	18.60			0.90		16.74			
		2nd A											
		LHS											
		0.00	16.00	1.00	14.30			0.90		12.87			

Modified Estimate

Modified Estimate														
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ No
	Chainage											Rs.	Rs.	
	RHS													
	0.00	41.50		1.00	32.00			0.90		28.80				
	Bhuvaneshwari nagar													
	St Anthony Church Road													
	RHS													
	19.00	140.00	R/S	185				0.90	0.60	99.90				
	Kashinagar cross Roads and Surrounding Area													
				1	1210.00			0.90		1089.00				
											</			

Modified Estimate

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
												Rs.	Rs.	
	Culvert													
	1st Main Road													Cop
	RHS													Hol
	74.00	82.00	R/S	1	8.00			0.45	0.075	0.27	culvert			
	Cubic Apartment													
	Culverts													
	2nd Main Road Across The Road													
	103.70	105.50		2	10.00			0.45	0.075	1.50				Ne
	2nd Main Road													Bot
	LHS													Co
	19.00	25.50	L/S	2	6.50			0.45	0.075	0.98				
	87.00	91.00	L/S	2	4.00			0.45	0.075	0.60				For
	118.00	123.00	L/S	2	5.00			0.45	0.075	0.75				Ar
	148.60	154.00	L/S	2	5.40			0.45	0.075	0.81				
	Amruth Nagar Sector A													
	Culverts													
	Culvert													
				2	7.50			0.60	0.10	0.90				19
				2	6.20			0.60	0.10	0.74				
				2	5.00			0.60	0.10	0.60				
				2	6.20			0.60	0.10	0.74				
				2	3.80			0.60	0.10	0.46				
				2	5.00			0.60	0.10	0.60				
				2	3.80			0.60	0.10	0.46				
	Amruth Nagar Sector A													
	Culverts													
	Appartment Beside Road (LHS)													20
	199.50	204.40		2	4.90			0.45	0.10	0.44				
	169.30	174.90		2	5.60			0.45	0.10	0.50				
	219.70	225.70		2	6.00			0.45	0.10	0.54				
	Across the Road													
	225.70	227.50		2	6.60			0.45	0.10	0.59				
	Kallappa Layout													
	1st Cross Road													
	LHS													
	0.00	44.30		2	44.30			0.30	0.075	1.99				
	RHS													
	0.00	43.90		2	43.90			0.30	0.075	1.98				
	1st A Cross Road													
	LHS													
	0.00	64.00		2	64.00			0.30	0.075	2.88				
	2nd Cross Road													
	RHS													
	0.00	43.60		2	43.60			0.30	0.075	1.96				
	2nd A Cross Road													
	LHS													
	0.00	76.50		2	76.50			0.30	0.075	3.44				
	RHS													
	0.00	76.50		2	76.50			0.30	0.075	3.44				
	Sanjeevini nagar													

Rs.	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
		Chainage										Rs.	Rs.
			L/S	1	50.00			1.16	0.23	13.34			
			R/S	1	62.00			0.50	0.23	7.13			
		19th Main Road											
				1	0.80			1.20	0.23	0.22			
				1	1.50			1.00	0.23	0.35			
		Edge Lines											
			L/S	1	88.00			0.60	0.23	12.14			
			R/S	1	66.70			1.05	0.23	16.11			
		19th Cross Road											
				1	0.40			0.30	0.23	0.03			
				1	0.30			6.20	0.23	0.43			
				1	1.30			0.40	0.23	0.12			
				1	5.40			0.40	0.23	0.50			
				1	0.30			1.60	0.23	0.11			
		Edge Lines											
			L/S	1	40.30			0.28	0.23	2.61			
			R/S	1	27.10			0.56	0.23	3.48			
		19th A											
				1	1.20			2.00	0.23	0.55			
		Edge Lines											
			L/S	1	82.40			0.57	0.23	10.88			
			R/S	1	41.10			0.28	0.23	2.67			
		20th Main Road (bescom)											
	0.00	74.00		1	74.00			4.83	0.23	82.12			
		21st Main Road											
				1	0.30			7.00	0.23	0.48			
		20th Cross Road											
				1	0.20			8.50	0.23	0.39			
				1	0.30			9.00	0.23	0.62			
				1	0.25			10.60	0.23	0.61			
		Edge Lines											
	0.00	85.50	R/S	1	85.50			1.00	0.23	19.67			
		Happy Childhood Road											
				1	4.00			1.50	0.23	1.38			
				1	0.30			5.60	0.23	0.39			
		Edge Lines											
	0.00	95.20	L/S	1	95.20			1.43	0.23	31.31			
	0.00	95.20	R/S	1	95.20			1.42	0.23	31.14			
		Ayyappa Swamy Temple Road											
		5th Cross Road											
				1	31.00			5.83	0.23	41.60			
		Cubic Apartment											
		1st Main Road											
	0.00	177.00		1	177.00			10.33	0.23	420.53			
		Connecting Road From 1st Mn to 2nd Main Road											
	0.00	26.40		1	26.40			7.70	0.23	46.75			
		2nd Main Road											
	0.00	209.20		1	209.20			9.58	0.23	460.71			
		1st Cross Road											
	0.00	46.30		1	46.30			6.52	0.23	69.38			

BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
			1	39.80			4.30	0.23	39.32			
	Bad Reaches											
			1	3.20			0.40	0.23	0.29			
			1	6.60			0.40	0.23	0.61			
			1	2.00			1.10	0.23	0.51			
	Edge Lines											
		L/S	1	49.70			0.25	0.23	2.86			
		R/S	1	41.70			0.30	0.23	2.88			
	1st B Cross Road											
			1	15.00			0.90	0.23	3.11			
			1	15.00			0.90	0.23	3.11			
			1	6.00			0.90	0.23	1.24			
			1	15.00			4.50	0.23	15.53			
			1	13.50			4.50	0.23	13.97			
	Edge Lines											
		L/S	1	19.40			0.20	0.23	0.89			
		R/S	1	25.40			0.40	0.23	2.34			
	2nd B Cross Road											
			1	1.10			1.20	0.23	0.30			
			1	1.00			2.20	0.23	0.51			
			1	1.00			2.90	0.23	0.67			
	Edge Lines											
	LHS											
		L/S	1	6.80			0.60	0.23	0.94			
		L/S	1	12.00			0.40	0.23	1.10			
		L/S	1	2.00			0.60	0.23	0.28			
		L/S	1	2.10			0.30	0.23	0.14			
		L/S	1	3.00			0.55	0.23	0.38			
		L/S	1	4.80			0.20	0.23	0.22			
		L/S	1	6.20			0.40	0.23	0.57			
	RHS											
		R/S	1	4.20			0.60	0.23	0.58			
		R/S	1	0.80			1.10	0.23	0.20			
		R/S	1	4.00			0.30	0.23	0.28			
		R/S	1	2.50			5.80	0.23	3.34			
		R/S	1	15.00			0.40	0.23	1.38			
		R/S	1	9.00			0.40	0.23	0.83			
	3rd Cross Road											
			1	0.40			2.20	0.23	0.20			
			1	0.90			2.10	0.23	0.43			
			1	1.10			0.40	0.23	0.10			
			1	0.20			5.30	0.23	0.24			
			1	0.30			2.50	0.23	0.17			
			1	0.40			5.40	0.23	0.50			
			1	4.70			4.80	0.23	5.19			
	Edge Lines											
	LHS											
		L/S	1	12.10			0.30	0.23	0.83			
		L/S	1	15.60			0.45	0.23	1.61			
	RHS											
		R/S	1	12.3			0.20	0.23	0.57			
	4th A Cross Road											
			1	0.30			2.20	0.23	0.15			
			1	1.10			1.70	0.23	0.43			
			1	0.80			1.30	0.23	0.24			
			1	0.90			4.80	0.23	0.99			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
	Chainage											Rs.	Rs.	
				1	0.80			0.70	0.23	0.13				
				1	0.35			2.20	0.23	0.18				
				1	13.20			6.60	0.23	20.04				
	Edge Lines													
	LHS													
			L/S	1	6.00			0.58	0.23	0.80				
			L/S	1	8.00			0.27	0.23	0.50				
			L/S	1	2.10			0.20	0.23	0.10				
			L/S	1	14.40			0.30	0.23	0.99				
	RHS													
			R/S	1	6.00			0.20	0.23	0.28				
			R/S	1	4.20			0.20	0.23	0.19				
			R/S	1	3.40			0.25	0.23	0.20				
			R/S	1	14.40			0.20	0.23	0.66				
	5th Cross Road													
	15.00	30.00		1	15.00			5.93	0.23	20.44				
	6th Cross Road													
	30.00	45.00		1	15.00			5.95	0.23	20.53				
	Kempapura													
	1st Cross Road													
	20.00	30.00		1	10.00			3.90	0.23	8.97				
	2nd Cross Road													
				1	1.15			4.80	0.23	1.27				
				1	0.20			5.00	0.23	0.23				
	Edge Lines													
	LHS													
			L/S	1	8.40			0.30	0.23	0.58				
			L/S	1	6.00			0.25	0.23	0.35				
	RHS													
			R/S	1	15.00			0.55	0.23	1.90				
			R/S	1	2.00			0.55	0.23	0.25				
	3rd Cross Road													
				1	6.00			3.40	0.23	4.69				
	Edge Lines													
	RHS													
			R/S	1	9.60			0.38	0.23	0.84				
			R/S	1	9.00			1.00	0.23	2.07				
			R/S	1	12.60			0.25	0.23	0.72				
	4th Cross Road													
				1	1.20			2.20	0.23	0.61				
				1	4.20			0.20	0.23	0.19				
	Edge Lines													
	LHS													
			L/S	1	7.80			0.30	0.23	0.54				
	RHS													
			R/S	1	9.00			0.40	0.23	0.83				
			R/S	1	13.20			0.60	0.23	1.82				
	Amruthanagara A sector													
	Road													
	Bad Reaches													
	1st Main Road													
	LHS													
			L/S	1	1.10			1.10	0.23	0.28				
			L/S	1	1.20			1.00	0.23	0.28				
			L/S	1	1.20			1.30	0.23	0.36				
			L/S	1	1.50			0.90	0.23	0.31				
			L/S	1	1.20			1.20	0.23	0.33				

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
		L/S	1	1.00			1.00	0.23	0.23			
		L/S	1	1.30			1.20	0.23	0.36			
		L/S	1	1.20			1.30	0.23	0.36			
		L/S	1	1.20			1.00	0.23	0.28			
		L/S	1	1.50			1.30	0.23	0.45			
		L/S	1	1.20			1.30	0.23	0.36			
		L/S	1	1.00			1.20	0.23	0.28			
		L/S	1	1.20			1.10	0.23	0.30			
		L/S	1	1.00			1.00	0.23	0.23			
		L/S	1	1.20			1.30	0.23	0.36			
	RHS											
		R/S	1	1.00			1.30	0.23	0.30			
		R/S	1	0.80			1.30	0.23	0.24			
		R/S	1	0.90			1.20	0.23	0.25			
		R/S	1	0.60			1.30	0.23	0.18			
		R/S	1	0.90			1.00	0.23	0.21			
		R/S	1	1.20			1.30	0.23	0.36			
		R/S	1	1.00			1.50	0.23	0.35			
		R/S	1	1.20			1.20	0.23	0.33			
		R/S	1	1.30			1.20	0.23	0.36			
		R/S	1	1.00			1.10	0.23	0.25			
		R/S	1	1.30			1.20	0.23	0.36			
		R/S	1	0.80			1.00	0.23	0.18			
		R/S	1	1.20			1.10	0.23	0.30			
		R/S	1	0.90			1.20	0.23	0.25			
		R/S	1	1.00			1.20	0.23	0.28			
	2nd Main Road in 1st Cross Road											
			1	1.50			1.30	0.23	0.45			
			1	1.20			1.20	0.23	0.33			
			1	1.00			1.00	0.23	0.23			
			1	0.80			1.20	0.23	0.22			
	1st											
			1	1.00			1.50	0.23	0.35			
	Sri Sai Sannidi Apartment Road Amruthnagar											
	Road B/W 1st cr & 2nd Cross rd											
			1	0.80			1.00	0.23	0.18			
			1	0.90			1.20	0.23	0.25			
	Road B/W 2nd Cross & 3rd Cross rd											
			1	1.20			1.10	0.23	0.30			
	Road B/W 3rd Cross & 4th Cross rd											
			1	1.10			1.30	0.23	0.33			
	Road B/W 4th Cross & 5th Cross											
			1	1.20			1.10	0.23	0.30			
	2nd Cross Road											
			1	1.00			1.20	0.23	0.28			
			1	1.20			1.20	0.23	0.33			
			1	1.30			1.20	0.23	0.36			
			1	1.00			0.90	0.23	0.21			
			1	1.30			1.20	0.23	0.36			
			1	1.50			0.90	0.23	0.31			
	3rd Cross Road											
			1	1.20			1.20	0.23	0.33			
			1	1.00			1.00	0.23	0.23			
			1	0.80			1.20	0.23	0.22			
			1	1.30			1.00	0.23	0.30			
	4th Cross Road											
			1	1.30			1.20	0.23	0.36			
			1	1.00			1.50	0.23	0.35			
			1	1.30			1.20	0.23	0.36			
			1	1.10			0.90	0.23	0.23			
			1	1.20			0.80	0.23	0.22			
			1	1.00			1.30	0.23	0.30			
	5th Cross Road											
			1	1.50			2.00	0.23	0.69			
			1	1.20			1.50	0.23	0.41			
			1	1.20			1.80	0.23	0.50			
			1	1.00			1.20	0.23	0.28			
			1	1.00			0.60	0.23	0.14			
	2nd B Cross Road											
	LHS											
			1	1.20			1.80	0.23	0.50			
			1	1.00			1.60	0.23	0.37			
			1	1.70			1.50	0.23	0.59			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	RHS											
			1	1.00			1.50	0.23	0.35			
			1	1.60			1.70	0.23	0.63			
			1	1.25			1.20	0.23	0.35			
	1st Main Road Beside BBMP Park											
	LHS											
			1	1.20			1.80	0.23	0.50			
			1	1.00			1.60	0.23	0.37			
			1	1.80			1.50	0.23	0.62			
	RHS											
			1	1.00			1.50	0.23	0.35			
			1	1.60			1.70	0.23	0.63			
			1	1.25			1.20	0.23	0.35			
	2nd Main Road											
			1	1.00			1.30	0.23	0.30			
			1	1.70			1.00	0.23	0.39			
			1	1.50			1.20	0.23	0.41			
	8th Cross Road											
	LHS											
			1	1.00			1.50	0.23	0.35			
			1	1.80			1.00	0.23	0.41			
			1	1.20			1.80	0.23	0.50			
	RHS											
			1	1.50			1.00	0.23	0.35			
			1	1.20			1.50	0.23	0.41			
			1	1.00			1.20	0.23	0.28			
	8th A Cross Road											
	LHS											
			1	1.00			1.20	0.23	0.28			
			1	0.80			1.00	0.23	0.18			
	Amruthanagara A sector											
	Maruthi Farm 5th cross Rd											
	0.00 87.10		1	87.10			4.78	0.23	95.76			
	Appartment Beside Road (RHS)											
	0.00 121.00		1	121.00			3.66	0.23	101.91			
	Appartment Beside Road (LHS)											
	0.00 180.00		1	180.00			5.81	0.23	240.33			
	UGD Cut Portion											
	Maruthi Farm 8th Cross Road											
	0.00 138.00		1	138.00			1.50	0.23	47.61			
	Amruthanagara A sector											
	Amruthahalli Police Station Back side											
	1st Main Road (0-430)											
	0.00 426.00		1	426.00			8.97	0.30	1146.69			
	Coffee Board Layout											
	Road Portion											
	Bad Reaches											
	5th Cross											
			1	1.80			2.00	0.23	0.83			
			1	1.90			2.30	0.23	1.01			
			1	1.50			1.80	0.23	0.62			
			1	2.00			1.30	0.23	0.60			
			1	2.10			1.50	0.23	0.72			
			1	2.20			1.00	0.23	0.51			
			1	1.80			1.60	0.23	0.66			
	6th Cross											
			1	1.30			1.20	0.23	0.36			
			1	1.20			1.00	0.23	0.28			
	7th Cross											
			1	1.20			1.30	0.23	0.36			
			1	1.80			1.10	0.23	0.46			
	8th Cross											
			1	1.50			1.50	0.23	0.52			
			1	1.80			1.80	0.23	0.75			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	ORTUR Apartment Road											
0.00	628.00	L/S	1	628.00			2.02	0.30	381.13			
0.00	628.00	L/S	1	628.00			1.66	0.30	312.74			
	Approachs											
			1	6.00			1.35	0.30	2.43			
			1	2.20			2.70	0.30	1.78			
			1	5.50			1.80	0.30	2.97			
			1	8.10			1.90	0.30	4.62			
			1	3.80			1.80	0.30	2.05			
			1	3.90			1.30	0.30	1.52			
			1	3.50			5.00	0.30	5.25			
			1	2.10			3.30	0.30	2.08			
			1	6.70			0.45	0.30	0.90			
	Viensa Lake View Appatament Parrallel Road											
0.00	54.50		1	54.50			7.58	0.30	123.92			
	Jakkur Double Rd											
	19th Cross Road											
0.00	177.90		1	177.90			6.56	0.30	350.13			
	Approach Road											
0.00	52.30		1	52.30			7.21	0.30	113.14			
	19th A Cross Road											
0.00	138.80		1	138.80			4.56	0.30	189.67			
	Kuvempu Rd											
	Road Cut Portion											
	3rd Cross Road (Super Market Road)											
	Road Edge											
	Kuvempu Road											
0.00	256.00	L/S	1	256.00			0.94	0.30	71.81			
0.00	256.00	R/S	1	256.00			1.36	0.30	104.68			
	Gopalappa to Cof Board											
	Road Work											
	St Antony Chaurch Road											
	(From Coffe Board Layout Park End)											
0.00	587.50		1	587.50			7.50	0.30	1,321.17			
	Cross Road St Antony Charch Road											
0.00	142.50		1	142.50			6.40	0.30	273.69			
	Mandi Mariyappa Rd											
	7th Cross Road (Mandi Mariyappa Palya)											
0.00	27.00		1	27.00			3.58	0.30	29.00			
	Road Cut Portion											
	3rd Main Road (Mandi Mariyappa Reddy Road)											
0.00	802.80		1	802.80			4.52	0.30	1,087.39			
	Jain School Road											
0.00	38.10		1	38.10			6.29	0.30	71.89			
	Deduct NP3 UGD Cut portion											
			-1	38.10			0.50	0.30	-5.72			
	Kempapura Main Road											
0.00	146.00		1	144.80			5.28	0.30	764.54			
	Deduct NP3 UGD Cut portion											
			-1	144.80			0.50	0.30	-21.72			
	Road Edge Portion											
	Kempapura Main Road											
146.00	515.00	L/S	1	369.00			0.80	0.30	88.56			
146.00	515.00	R/S	1	369.00			0.60	0.30	66.42			
	Cut Portion											
	Kempapura Main Road											
515.00	700.00		1	185.00			2.50	0.30	138.75			

Modified Estimate													Page 30 of 1
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	
	Chainage										Rs.	Rs.	
		L/S	1	15.00			0.26	0.23	0.90				
		L/S	1	7.10			0.26	0.23	0.42				
		L/S	1	16.00			1.23	0.23	4.53				
		L/S	1	15.00			0.23	0.23	0.79				
	RHS	L/S	1	2.40			0.23	0.23	0.13				
		R/S	1	4.00			3.05	0.23	2.81				
		R/S	1	15.00			1.36	0.23	4.69				
		R/S	1	15.00			1.36	0.23	4.69				
		R/S	1	15.00			1.36	0.23	4.69				
		R/S	1	12.50			1.36	0.23	3.91				
		R/S	1	15.00			1.50	0.23	5.18				
		R/S	1	7.70			1.50	0.23	2.66				
		R/S	1	15.00			1.30	0.23	4.49				
		R/S	1	15.00			1.30	0.23	4.49				
		R/S	1	15.00			1.30	0.23	4.49				
		R/S	1	2.20			1.30	0.23	0.66				
		R/S	1	11.50			1.93	0.23	5.10				
	16th Main Road												
			1	0.20			0.30	0.23	0.01				
			1	0.70			4.40	0.23	0.71				
			1	0.20			4.60	0.23	0.21				
	Edge Lines												
	LHS												
		L/S	1	156.90			0.53	0.23	19.13				
		R/S	1	189.30			0.38	0.23	16.46				
	17th Main Road												
			1	1.00			0.80	0.23	0.18				
			1	0.30			3.40	0.23	0.23				
			1	2.90			0.40	0.23	0.27				
			1	0.30			3.60	0.23	0.25				
			1	0.40			0.40	0.23	0.04				
			1	0.20			5.20	0.23	0.24				
			1	0.30			3.80	0.23	0.26				
			1	1.20			0.30	0.23	0.08				
	Edge Lines												
		L/S	1	102.60			0.61	0.23	14.39				
		R/S	1	105.00			0.36	0.23	8.69				
	18th Main Road												
			1	0.80			0.90	0.23	0.17				
			1	5.10			0.50	0.23	0.59				
			1	5.20			0.50	0.23	0.60				
			1	2.60			2.10	0.23	1.26				
	Edge Lines												
		L/S	1	130.80			0.42	0.23	12.64				
		R/S	1	143.60			0.66	0.23	21.80				
	18th Cross Road												
			1	1.00			0.80	0.23	0.18				
			1	0.80			1.20	0.23	0.22				
			1	0.30			6.50	0.23	0.45				
			1	4.50			2.90	0.23	3.00				
	Edge Lines												

Rs.	BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
				1	15.00			1.36	0.23	4.69			
				1	12.50			1.36	0.23	3.91			
				1	15.00			1.50	0.23	5.18			
				1	7.70			1.50	0.23	2.66			
95645.59				1	15.00			1.30	0.23	4.49			
				1	15.00			1.30	0.23	4.49			
				1	15.00			1.30	0.23	4.49			
				1	2.20			1.30	0.23	0.66			
				1	11.50			1.93	0.23	5.10			
		16th Main Road											
				1	0.20			0.30	0.23	0.01			
				1	0.70			4.40	0.23	0.71			
				1	0.20			4.60	0.23	0.21			
		Edge Lines											
		LHS											
				1	156.90			0.53	0.23	19.13			
				1	189.30			0.38	0.23	16.46			
		17th Main Road											
				1	1.00			0.80	0.23	0.18			
				1	0.30			3.40	0.23	0.23			
				1	2.90			0.40	0.23	0.27			
				1	0.30			3.60	0.23	0.25			
				1	0.40			0.40	0.23	0.04			
				1	0.20			5.20	0.23	0.24			
				1	0.30			3.80	0.23	0.26			
				1	1.20			0.30	0.23	0.08			
		Edge Lines											
				1	102.60			0.61	0.23	14.39			
				1	105.00			0.36	0.23	8.69			
		18th Main Road											
				1	0.80			0.90	0.23	0.17			
				1	5.10			0.50	0.23	0.59			
				1	5.20			0.50	0.23	0.60			
				1	2.60			2.10	0.23	1.26			
		Edge Lines											
				1	130.80			0.42	0.23	12.64			
				1	143.60			0.66	0.23	21.80			
		18th Cross Road											
				1	1.00			0.80	0.23	0.18			
				1	0.80			1.20	0.23	0.22			
				1	0.30			6.50	0.23	0.45			
				1	4.50			2.90	0.23	3.00			
		Edge Lines											
				1	50.00			1.16	0.23	13.34			
				1	62.00			0.50	0.23	7.13			
		19th Main Road											
				1	0.80			1.20	0.23	0.22			
				1	1.50			1.00	0.23	0.35			
		Edge Lines											
				1	88.00			0.60	0.23	12.14			
				1	66.70			1.05	0.23	16.11			
		19th Cross Road											
				1	0.40			0.30	0.23	0.03			
				1	0.30			6.20	0.23	0.43			
				1	1.30			0.40	0.23	0.12			
				1	5.40			0.40	0.23	0.50			
				1	0.30			1.60	0.23	0.11			
		Edge Lines											
				1	40.30			0.28	0.23	2.61			
				1	27.10			0.56	0.23	3.48			
		19th A Cross Road											
				1	1.20			2.00	0.23	0.55			
		Edge Lines											
				1	82.40			0.57	0.23	10.88			
				1	41.10			0.28	0.23	2.67			

[illegible]

Modified Estimate

Rs.	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
		Chainage										Rs.	Rs.
				1	1.20			2.00	0.23	0.55			
				1	1.50			1.80	0.23	0.62			
				1	1.70			1.10	0.23	0.43			
		3rd Main Road											
				1	1.80			2.00	0.23	0.83			
				1	1.80			1.50	0.23	0.62			
				1	1.35			1.80	0.23	0.56			
				1	1.90			1.20	0.23	0.52			
				1	1.20			1.80	0.23	0.50			
		4th Main Road											
				1	1.50			1.80	0.23	0.62			
				1	2.00			2.20	0.23	1.01			
				1	2.30			1.80	0.23	0.95			
				1	3.00			1.95	0.23	1.35			
				1	2.00			1.75	0.23	0.81			
				1	2.20			1.70	0.23	0.86			
				1	2.30			1.50	0.23	0.79			
				1	1.80			1.20	0.23	0.50			
		5th Main Road											
				1	1.50			1.10	0.23	0.38			
				1	1.20			1.60	0.23	0.44			
				1	1.30			1.30	0.23	0.39			
				1	1.00			1.20	0.23	0.28			
				1	1.80			1.50	0.23	0.62			
				1	2.05			1.00	0.23	0.47			
				1	1.90			1.20	0.23	0.52			
				1	1.80			1.30	0.23	0.54			
		Pampa Extension Road											
		Vinayaka layout											
		1st Main Road											
				1	39.80			4.30	0.23	39.32			
		Bad Reaches											
				1	3.20			0.40	0.23	0.29			
				1	6.60			0.40	0.23	0.61			
				1	2.00			1.10	0.23	0.51			
		Edge Lines											
				1	49.70			0.25	0.23	2.86			
				1	41.70			0.30	0.23	2.88			
		1st B Cross Road											
				1	15.00			0.90	0.23	3.11			
				1	15.00			0.90	0.23	3.11			
				1	6.00			0.90	0.23	1.24			
				1	15.00			4.50	0.23	15.53			
				1	13.50			4.50	0.23	13.97			
		Edge Lines											
				1	19.40			0.20	0.23	0.89			
				1	25.40			0.40	0.23	2.34			
		2nd B Cross Road											
				1	1.10			1.20	0.23	0.30			
				1	1.00			2.20	0.23	0.51			
				1	1.00			2.90	0.23	0.67			
		Edge Lines											
		LHS											
				1	6.80			0.60	0.23	0.94			
				1	12.00			0.40	0.23	1.10			
				1	2.00			0.60	0.23	0.28			
				1	2.10			0.30	0.23	0.14			
				1	3.00			0.55	0.23	0.38			
				1	4.80			0.20	0.23	0.22			
				1	6.20			0.40	0.23	0.57			
		RHS											
				1	4.20			0.60	0.23	0.58			
				1	0.80			1.10	0.23	0.20			
				1	4.00			0.30	0.23	0.28			
				1	2.50			5.80	0.23	3.34			
				1	15.00			0.40	0.23	1.38			
				1	9.00			0.40	0.23	0.83			
		3rd Cross Road											
				1	0.40			2.20	0.23	0.20			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	1st Main Road											
	LHS		1	1.10			1.10	0.23	0.28			
			1	1.20			1.00	0.23	0.28			
			1	1.20			1.30	0.23	0.36			
			1	1.50			0.90	0.23	0.31			
			1	1.20			1.20	0.23	0.33			
			1	1.00			1.00	0.23	0.23			
			1	1.30			1.20	0.23	0.36			
			1	1.20			1.30	0.23	0.36			
			1	1.20			1.00	0.23	0.28			
			1	1.50			1.30	0.23	0.45			
			1	1.20			1.30	0.23	0.36			
			1	1.00			1.20	0.23	0.28			
			1	1.20			1.10	0.23	0.30			
			1	1.00			1.00	0.23	0.23			
			1	1.20			1.30	0.23	0.36			
	RHS		1	1.00			1.30	0.23	0.30			
			1	0.80			1.30	0.23	0.24			
			1	0.90			1.20	0.23	0.25			
			1	0.60			1.30	0.23	0.18			
			1	0.90			1.00	0.23	0.21			
			1	1.20			1.30	0.23	0.36			
			1	1.00			1.50	0.23	0.35			
			1	1.20			1.20	0.23	0.33			
			1	1.30			1.20	0.23	0.36			
			1	1.00			1.10	0.23	0.25			
			1	1.30			1.20	0.23	0.36			
			1	0.80			1.00	0.23	0.18			
			1	1.20			1.10	0.23	0.30			
			1	0.90			1.20	0.23	0.25			
			1	1.00			1.20	0.23	0.28			
	2nd Main Road in 1st Cross Road		1	1.50			1.30	0.23	0.45			
			1	1.20			1.20	0.23	0.33			
			1	1.00			1.00	0.23	0.23			
			1	0.80			1.20	0.23	0.22			
	1st Cross Road Block B Apartment		1	1.00			1.50	0.23	0.35			
	Sri Sai Sannidi Apartment Road Amruthnagar											
	Road B/W 1st cr & 2nd Cross rd		1	0.80			1.00	0.23	0.18			
			1	0.90			1.20	0.23	0.25			
	Road B/W 2nd Cross & 3rd Cross rd		1	1.20			1.10	0.23	0.30			
	Road B/W 3rd Cross & 4th Cross rd		1	1.10			1.30	0.23	0.33			
	Road B/W 4th Cross & 5th Cross		1	1.20			1.10	0.23	0.30			
	2nd Cross Road		1	1.00			1.20	0.23	0.28			
			1	1.20			1.20	0.23	0.33			
			1	1.30			1.20	0.23	0.36			
			1	1.00			0.90	0.23	0.21			
			1	1.30			1.20	0.23	0.36			
			1	1.50			0.90	0.23	0.31			
	3rd Cross Road		1	1.20			1.20	0.23	0.33			
			1	1.00			1.00	0.23	0.23			
			1	0.80			1.20	0.23	0.22			
			1	1.30			1.00	0.23	0.30			
	4th Cross Road		1	1.30			1.20	0.23	0.36			
			1	1.00			1.50	0.23	0.35			
			1	1.30			1.20	0.23	0.36			
			1	1.10			0.90	0.23	0.23			
			1	1.20			0.80	0.23	0.22			
			1	1.00			1.30	0.23	0.30			
	5th Cross Road		1	1.50			2.00	0.23	0.69			
			1	1.20			1.50	0.23	0.41			
			1	1.20			1.80	0.23	0.50			

Page 47 of 102

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
			1	1.50			1.50	0.23	0.52			
			1	1.80			1.80	0.23	0.75			
			1	1.30			2.00	0.23	0.60			
			1	1.80			1.50	0.23	0.62			
			1	1.50			2.00	0.23	0.69			
			1	1.10			1.30	0.23	0.33			
Kuvempu road(raghvendra circle to coffee board layout main road)												
			1	2.00			1.30	0.23	0.60			
			1	1.80			2.00	0.23	0.83			
			1	1.50			2.50	0.23	0.86			
			1	1.20			2.30	0.23	0.63			
			1	1.30			2.20	0.23	0.66			
			1	1.50			2.10	0.23	0.72			
			1	2.00			2.00	0.23	0.92			
			1	2.00			1.85	0.23	0.85			
			1	2.50			1.90	0.23	1.09			
			1	1.80			2.00	0.23	0.83			
			1	1.90			2.30	0.23	1.01			
			1	1.50			2.00	0.23	0.69			
			1	2.00			1.30	0.23	0.60			
			1	2.10			1.50	0.23	0.72			
			1	2.20			2.30	0.23	1.16			
			1	2.30			2.80	0.23	1.48			
			1	2.80			2.40	0.23	1.55			
			1	1.50			2.30	0.23	0.79			
			1	1.80			2.20	0.23	0.91			
			1	2.80			2.00	0.23	1.29			
			1	3.00			1.85	0.23	1.28			
			1	2.30			2.00	0.23	1.06			
			1	2.60			2.00	0.23	1.20			
Coffe Board Zroad from green trends up to kannada flag												
			1	3.10			2.15	0.23	1.53			
			1	2.80			2.50	0.23	1.61			
			1	2.75			2.35	0.23	1.49			
			1	3.00			2.20	0.23	1.52			
			1	2.80			2.25	0.23	1.45			
			1	2.75			2.80	0.23	1.77			
			1	2.35			2.35	0.23	1.27			
			1	2.15			2.50	0.23	1.24			
			1	3.50			2.50	0.23	2.01			
			1	3.00			2.65	0.23	1.83			
kannada flag to Main Road												
			1	1.30			2.10	0.23	0.63			
			1	2.30			2.35	0.23	1.24			
			1	2.50			2.40	0.23	1.38			
			1	2.20			2.50	0.23	1.27			
Hoysala Layout												
1st Cross Road												
0.00	317.30		1	317.30			4.72	0.23	344.39			
2nd Cross Road												
0.00	83.50		1	83.50			3.71	0.23	71.27			
3rd Cross Road												
0.00	55.50		1	55.50			4.67	0.23	59.59			
4th Cross Road												
0.00	34.00		1	34.00			5.76	0.23	45.02			
5th Cross Road												
0.00	53.00		1	53.00			4.53	0.23	55.22			
6th Cross Road												
0.00	32.00		1	32.00			5.65	0.23	41.61			
7th Cross Road												
0.00	64.30		1	64.30			5.03	0.23	74.39			
18th c/s to JNC circle												
ORTUR Apartment Road												
0.00	628.00		1	628.00			2.02	0.23	292.20			
0.00	628.00		1	628.00			1.66	0.23	239.77			

Modified Estimate													
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
Approachs													
				1	6.00			1.35	0.23	1.86			
				1	2.20			2.70	0.23	1.37			
				1	5.50			1.80	0.23	2.28			
				1	8.10			1.90	0.23	3.54			
				1	3.80			1.80	0.23	1.57			
				1	3.90			1.30	0.23	1.17			
				1	3.50			5.00	0.23	4.03			
				1	2.10			3.30	0.23	1.59			
				1	6.70			0.45	0.23	0.69			
Viensa Lake View Appatament Parrallel Road													
	0.00	54.50		1	54.50			7.58	0.23	95.00			
Jakkur Double Rd													
19th Cross Road													
	0.00	177.90		1	177.90			6.56	0.23	268.44			
Approach Road													
	0.00	52.30		1	52.30			7.21	0.23	86.74			
19th A Cross Road													
	0.00	138.80		1	138.80			4.56	0.23	145.41			
Kuvempu Rd													
Road Cut Portion													
3rd Cross Road (Super Market Road)													
Road Edge													
Kuvempu Road													
	0.00	256.00		1	256.00			0.94	0.23	55.05			
	0.00	256.00		1	256.00			1.36	0.23	80.25			
Gopalappa to Cof Board													
Road Work													
St Antony Chaurch Road													
(From Coffe Board Layout Park End)													
	0.00	587.50		1	587.50			7.50	0.23	1,012.90			
Cross Road St Antony Charch Road													
	0.00	142.50		1	142.50			6.40	0.23	209.83			
Mandi Mariyappa Rd													
7th Cross Road (Mandi Mariyappa Palya)													
	0.00	27.00		1	27.00			3.58	0.23	22.23			
Road Cut Portion													
3rd Main Road (Mandi Mariyappa Reddy Road)													
	0.00	802.80		1	802.80			4.52	0.23	833.67			
Jain School Road													
	0.00	38.10		1	38.10			6.29	0.20	47.93			
Deduct NP3 UGD Cut portion													
				-1.00	38.10			0.50	0.20	-3.81			
Kempapura Main Road													
	0.00	146.00		1	144.80			5.28	0.20	152.91			
Deduct NP3 UGD Cut portion													
				-1.00	144.80			0.50	0.20	-14.48			
UGD Cut Portion for NP3 Pipe installations													
Jain School Road													
	0.00	38.10		1	38.10			0.60	0.23	5.26			
Kempapura Main Road													
	0.00	558.80		1	558.80			0.60	0.23	77.11			
Deduct Manhole Volume													
				-26	1.20			0.60	0.23	-4.31			
Road Edge Portion													
Kempapura Main Road													

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	146.00	515.00	L/S	1	369.00			0.80	0.20	59.04			
	146.00	515.00	R/S	1	369.00			0.60	0.20	44.28			
	Cut Portion												
	Kempapura Main Road												
	515.00	700.00		1	185.00			2.50	0.20	92.50			
	Cut Portion												
	Vidyanikethan School Road												
	0.00	42.00		1.00	42.00			2.50	0.20	21.00			
	Approach			1	7.20			2.50	0.20	3.60			
				1	2.50			2.00	0.20	1.00			
	Sindhi College Gate												
	0.00	277.00		1	277.00			1.50	0.20	83.10			
	Venkatappa Badavane 1st c/s Rd												
	0.00	70.80		1.00	70.80			0.30	0.20	4.25			
	Venkatappa Badavane 2nd c/s Rd												
	0.00	73.00		1	73.00			0.22	0.20	3.21			
	Venkatappa Badavane 3rd c/s Rd												
	0.00	45.00		1	45.00			0.70	0.20	6.30			
	Heera Caters Rd (Mariyappanapalya)												
	0.00	79.00		1	79.00			6.40	0.20	101.12			
	From Shanthivana Rd end at Sardar Vallabhbhai Patel												
	0.00	401.50		1	270.00			1.50	0.20	81.00			
								Total		9001.31			
								BOQ		5302.07			
								Upto 125%		6627.59	Cum	1891.85	12538404.72
								Above 125%		2373.72	Cum	1891.85	4490721.45
26	KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kgsqm using mechanical means complete as per specifications. As per MORTH specification clause No. 502 (P.No.161, I.No.21.6 of PW,P&I WTD SR 2016-17)												
	Big Market Sahakarnagar 60ft												
	Hegde nagar												
	For bescom and ugd cut restoration												
	0.00	630.00		1	630.00			2.42		1521.45			
	SAHAKARNAGAR 'A' BLOCK 15TH MAIN												
	0.00	203.00		1	203.00			8.32		1688.96			
	Bad Reaches												
				12	1.85			1.50		33.30			
				16	1.95			2.45		76.44			
				13	1.75			1.35		30.71			
				1	19.00			2.50		47.50			
	Big Market Sahakarnagar 60ft												
	Sahakaranagar												
	15th Main Road												
				1	0.40			4.55		1.82			
	Edge Lines												
	LHS												
	15.00	45.00		1	30.00			0.90		27.00			
	RHS												
	45.00	50.00		1	5.00			0.45		2.25			
	50.00	77.50		1	27.50			0.30		8.25			

Modified Estimate

Modified Estimate														
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
	Chainage											Rs.	Rs.	
	15th Cross Road													
				2	0.80			2.40		3.84				
				3	1.70			0.70		3.57				
				1	0.80			0.70		0.56				
	Edge Lines													
	LHS													
	0.00	0.00		1	80.80			1.17		94.54				
	0.00	0.00		1	75.60			1.07		80.89				
	16 th Cross Road													
	Bad Reaches													
	0.00	28.00		1	28.00			8.57		239.96				
				1	0.80			1.70		1.36				
				1	0.70			5.10		3.57				
				1	0.80			1.40		1.12				
				1	0.80			1.30		1.04				
	Edge Line													
	LHS													
				1	12.30			0.90		11.07				
				1	15.00			1.00		15.00				
				1	3.30			1.00		3.30				
				1	2.80			1.40		3.92				
				1	15.00			0.26		3.90				
				1	7.10			0.26		1.85				
				1	16.00			1.23		19.68				
				1	15.00			0.23		3.45				
				1	2.40			0.23		0.55				
	RHS													
				1	4.00			3.05		12.20				
				1	15.00			1.36		20.40				
				1	15.00			1.36		20.40				
				1	15.00			1.36		20.40				
				1	12.50			1.36		17.00				
				1	15.00			1.50		22.50				
				1	7.70			1.50		11.55				
				1	15.00			1.30		19.50				
				1	15.00			1.30		19.50				
				1	15.00			1.30		19.50				
				1	2.20			1.30		2.86				
				1	11.50			1.93		22.20				
	16th Main Road													
				1	0.20			0.30		0.06				
				1	0.70			4.40		3.08				
				1	0.20			4.60		0.92				
	Edge Lines													
	LHS													
				1	156.90			0.53		83.16				
				1	189.30			0.38		71.56				
	17th Main Road													
				1	1.00			0.80		0.80				
				1	0.30			3.40		1.02				
				1	2.90			0.40		1.16				
				1	0.30			3.60		1.08				
				1	0.40			0.40		0.16				
				1	0.20			5.20		1.04				
				1	0.30			3.80		1.14				
				1	1.20			0.30		0.36				
	Edge Lines													
				1	102.60			0.61		62.59				
				1	105.00			0.36		37.80				
	18th Main Road													
				1	0.80			0.90		0.72				
				1	5.10			0.50		2.55				
				1	5.20			0.50		2.60				
				1	2.60			2.10		5.46				
	Edge Lines													
				1	130.80			0.42		54.94				

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
			1	143.60			0.66		94.78			
	18th Cross Road											
			1	1.00			0.80		0.80			
			1	0.80			1.20		0.96			
			1	0.30			6.50		1.95			
			1	4.50			2.90		13.05			
	Edge Lines											
			1	50.00			1.16		58.00			
			1	62.00			0.50		31.00			
	19th Main Road											
			1	0.80			1.20		0.96			
			1	1.50			1.00		1.50			
	Edge Lines											
			1	88.00			0.60		52.80			
			1	66.70			1.05		70.04			
	19th Cross Road											
			1	0.40			0.30		0.12			
			1	0.30			6.20		1.86			
			1	1.30			0.40		0.52			
			1	5.40			0.40		2.16			
			1	0.30			1.60		0.48			
	Edge Lines											
			1	40.30			0.28		11.36			
			1	27.10			0.56		15.15			
	19th A Cross Road											
			1	1.20			2.00		2.40			
	Edge Lines											
			1	82.40			0.57		47.30			
			1	41.10			0.28		11.59			
	20th Main Road (bescom)											
	0.00 74.00		1	74.00			4.83		357.05			
	21st Main Road											
			1	0.30			7.00		2.10			
	20th Cross Road											
			1	0.20			8.50		1.70			
			1	0.30			9.00		2.70			
			1	0.25			10.60		2.65			
	Edge Lines											
	0.00 85.50		1	85.50			1.00		85.50			
	Happy Childhood Road											
			1	4.00			1.50		6.00			
			1	0.30			5.60		1.68			
	Edge Lines											
	0.00 95.20		1	95.20			1.43		136.14			
	0.00 95.20		1	95.20			1.42		135.37			
	Ayyappa Swamy Temple Road											
	5th Cross Road											
	0.00 0.00		1	31.00			5.83		180.85			
	Cubic Apartment											
	1st Main Road											
	0.00 177.00		1	177.00			10.33		1828.41			
	Connecting Road From 1st Mn to 2nd Main Road											
	0.00 26.40		1	26.40			7.70		203.28			
	2nd Main Road											
	0.00 209.20		1	209.20			9.58		2003.09			
	1st Cross Road											
	0.00 46.30		1	46.30			6.52		301.64			
	Cubic Apartment											
	2nd Cross Road											
	0.00 44.90		1	44.90			5.48		246.19			
	3rd Cross Road											
	0.00 44.60		1	44.60			5.60		249.76			

Modified Estimate

Modified Estimate													
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	4th Cross Road												
	0.00	44.00		1	44.00			4.36		191.93			
	Pampa Extension Road												
	Road Portion												
	Bad Reaches												
	Pampa Extension												
	1st Cross Road												
				1	1.80			1.50		2.70			
				1	1.50			1.40		2.10			
	2nd Cross Road												
				1	1.30			1.50		1.95			
	3rd Cross Road												
				1	1.50			1.00		1.50			
	4th Cross Road												
				1	1.50			1.30		1.95			
				1	1.10			1.20		1.32			
				1	1.50			1.10		1.65			
	9th Cross Road												
				1	2.00			1.30		2.60			
				1	1.20			1.20		1.44			
				1	1.00			1.10		1.10			
				1	1.30			1.20		1.56			
	11th Cross Road												
				1	1.80			1.70		3.06			
				1	1.50			1.25		1.88			
				1	1.15			1.30		1.50			
	12th Cross Road												
				1	1.30			1.00		1.30			
				1	2.00			1.30		2.60			
				1	1.50			1.80		2.70			
				1	1.90			1.30		2.47			
	2nd Main Road												
				1	1.20			2.00		2.40			
				1	1.50			1.80		2.70			
				1	1.70			1.10		1.87			
	3rd Main Road												
				1	1.80			2.00		3.60			
				1	1.80			1.50		2.70			
				1	1.35			1.80		2.43			
				1	1.90			1.20		2.28			
				1	1.20			1.80		2.16			
	4th Main Road												
				1	1.50			1.80		2.70			
				1	2.00			2.20		4.40			
				1	2.30			1.80		4.14			
				1	3.00			1.95		5.85			
				1	2.00			1.75		3.50			
				1	2.20			1.70		3.74			
				1	2.30			1.50		3.45			
				1	1.80			1.20		2.16			
	5th Main Road												
				1	1.50			1.10		1.65			
				1	1.20			1.60		1.92			
				1	1.30			1.30		1.69			
				1	1.00			1.20		1.20			
				1	1.80			1.50		2.70			
				1	2.05			1.00		2.05			
				1	1.90			1.20		2.28			
				1	1.80			1.30		2.34			
	Pampa Extension Road												
	Vinayaka layout												
	1st Main Road												
				1	39.80			4.30		170.94			
	Bad Reaches												
				1	3.20			0.40		1.28			
				1	6.60			0.40		2.64			
				1	2.00			1.10		2.20			
	Edge Lines												
				1	49.70			0.25		12.43			
				1	41.70			0.30		12.51			

Rs.	BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
		Chainage										Rs.	Rs.
		1st B Cross Road											
				1	15.00			0.90		13.50			
				1	15.00			0.90		13.50			
				1	6.00			0.90		5.40			
				1	15.00			4.50		67.50			
				1	13.50			4.50		60.75			
		Edge Lines											
				1	19.40			0.20		3.88			
				1	25.40			0.40		10.16			
		2nd B Cross Road											
				1	1.10			1.20		1.32			
				1	1.00			2.20		2.20			
				1	1.00			2.90		2.90			
		Edge Lines											
		LHS											
				1	6.80			0.60		4.08			
				1	12.00			0.40		4.80			
				1	2.00			0.60		1.20			
				1	2.10			0.30		0.63			
				1	3.00			0.55		1.65			
				1	4.80			0.20		0.96			
				1	6.20			0.40		2.48			
		RHS											
				1	4.20			0.60		2.52			
				1	0.80			1.10		0.88			
				1	4.00			0.30		1.20			
				1	2.50			5.80		14.50			
				1	15.00			0.40		6.00			
				1	9.00			0.40		3.60			
		3rd Cross Road											
				1	0.40			2.20		0.88			
				1	0.90			2.10		1.89			
				1	1.10			0.40		0.44			
				1	0.20			5.30		1.06			
				1	0.30			2.50		0.75			
				1	0.40			5.40		2.16			
				1	4.70			4.80		22.56			
		Edge Lines											
		LHS											
				1	12.10			0.30		3.63			
				1	15.60			0.45		7.02			
		RHS											
				1	12.30			0.20		2.46			
		4th A Cross Road											
				1	0.30			2.20		0.66			
				1	1.10			1.70		1.87			
				1	0.80			1.30		1.04			
				1	0.90			4.80		4.32			
				1	0.80			0.70		0.56			
				1	0.35			2.20		0.77			
				1	13.20			6.60		87.12			
		Edge Lines											
		LHS											
				1	6.00			0.58		3.48			
				1	8.00			0.27		2.16			
				1	2.10			0.20		0.42			
				1	14.40			0.30		4.32			
		RHS											
				1	6.00			0.20		1.20			
				1	4.20			0.20		0.84			
				1	3.40			0.25		0.85			
				1	14.40			0.20		2.88			
		5th Cross Road											
		15.00 30.00		1	15.00			5.93		88.88			
		6th Cross Road											
		30.00 45.00		1	15.00			5.95		89.25			
		Kempapura											
		1st Cross Road											
		20.00 30.00		1	10.00			3.90		39.00			

Modified Estimate												Rate	Amount
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rs.	Rs.	
	Chainage												
	2nd Cross Road												
			1	1.15			4.80		5.52				
			1	0.20			5.00		1.00				
	Edge Lines												
	LHS		1	8.40			0.30		2.52				
			1	6.00			0.25		1.50				
	RHS		1	15.00			0.55		8.25				
			1	2.00			0.55		1.10				
	3rd Cross Road												
			1	6.00			3.40		20.40				
	Edge Lines												
	RHS		1	9.60			0.38		3.65				
			1	9.00			1.00		9.00				
			1	12.60			0.25		3.15				
	4th Cross Road												
			1	1.20			2.20		2.64				
			1	4.20			0.20		0.84				
	Edge Lines												
	LHS		1	7.80			0.30		2.34				
	RHS		1	9.00			0.40		3.60				
			1	13.20			0.60		7.92				
	Amruthanagara A sector												
	Road Portion												
	Bad Reaches												
	1st Main Road												
	LHS												
			1	1.10			1.10		1.21				
			1	1.20			1.00		1.20				
			1	1.20			1.30		1.56				
			1	1.50			0.90		1.35				
			1	1.20			1.20		1.44				
			1	1.00			1.00		1.00				
			1	1.30			1.20		1.56				
			1	1.20			1.30		1.56				
			1	1.20			1.00		1.20				
			1	1.50			1.30		1.95				
			1	1.20			1.30		1.56				
			1	1.00			1.20		1.20				
			1	1.20			1.10		1.32				
			1	1.00			1.00		1.00				
			1	1.20			1.30		1.56				
	RHS												
			1	1.00			1.30		1.30				
			1	0.80			1.30		1.04				
			1	0.90			1.20		1.08				
			1	0.60			1.30		0.78				
			1	0.90			1.00		0.90				
			1	1.20			1.30		1.56				
			1	1.00			1.50		1.50				
			1	1.20			1.20		1.44				
			1	1.30			1.20		1.56				
			1	1.00			1.10		1.10				
			1	1.30			1.20		1.56				
			1	0.80			1.00		0.80				
			1	1.20			1.10		1.32				
			1	0.90			1.20		1.08				
			1	1.00			1.20		1.20				
	2nd Main Road in 1st Cross Road												
			1	1.50			1.30		1.95				
			1	1.20			1.20		1.44				
			1	1.00			1.00		1.00				
			1	0.80			1.20		0.96				
	1st Cross Road Block B Apartment												
			1	1.00			1.50		1.50				
	Sri Sai Sannidi Apartment Road Amruthnagar												

BOQ Item No.	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	Road B/W 1st cr & 2nd Cross rd											
			1	0.80			1.00		0.80			
			1	0.90			1.20		1.08			
	Road B/W 2nd Cross & 3rd Cross rd											
			1	1.20			1.10		1.32			
	Road B/W 3rd Cross & 4th Cross rd											
			1	1.10			1.30		1.43			
	Road B/W 4th Cross & 5th Cross											
			1	1.20			1.10		1.32			
	2nd Cross Road											
			1	1.00			1.20		1.20			
			1	1.20			1.20		1.44			
			1	1.30			1.20		1.56			
			1	1.00			0.90		0.90			
			1	1.30			1.20		1.56			
			1	1.50			0.90		1.35			
	3rd Cross Road											
			1	1.20			1.20		1.44			
			1	1.00			1.00		1.00			
			1	0.80			1.20		0.96			
			1	1.30			1.00		1.30			
	4th Cross Road											
			1	1.30			1.20		1.56			
			1	1.00			1.50		1.50			
			1	1.30			1.20		1.56			
			1	1.10			0.90		0.99			
			1	1.20			0.80		0.96			
			1	1.00			1.30		1.30			
	5th Cross Road											
			1	1.50			2.00		3.00			
			1	1.20			1.50		1.80			
			1	1.20			1.80		2.16			
			1	1.00			1.20		1.20			
			1	1.00			0.60		0.60			
	2nd B Cross Road											
	LHS											
			1	1.20			1.80		2.16			
			1	1.00			1.60		1.60			
			1	1.70			1.50		2.55			
	RHS											
			1	1.00			1.50		1.50			
			1	1.60			1.70		2.72			
			1	1.25			1.20		1.50			
	1st Main Road Beside BBMP Park											
	LHS											
			1	1.20			1.80		2.16			
			1	1.00			1.60		1.60			
			1	1.80			1.50		2.70			
	RHS											
			1	1.00			1.50		1.50			
			1	1.60			1.70		2.72			
			1	1.25			1.20		1.50			
	2nd Main Road											
			1	1.00			1.30		1.30			
			1	1.70			1.00		1.70			
			1	1.50			1.20		1.80			
	8th Cross Road											
	LHS											
			1	1.00			1.50		1.50			
			1	1.80			1.00		1.80			
			1	1.20			1.80		2.16			
	RHS											
			1	1.50			1.00		1.50			
			1	1.20			1.50		1.80			
			1	1.00			1.20		1.20			
	8th A Cross Road											
	LHS											
			1	1.00			1.20		1.20			
			1	0.80			1.00		0.80			
	Amruthanagara A sector											
	Maruthi Farm 5th cross Rd											
	0.00	87.10	1	87.10			4.78		416.34			

Modified Estimate

Modified Estimate														
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
	Chainage											Rs.	Rs.	
	Appartment Beside Road (RHS)													
	0.00	121.00		1	121.00			3.66		443.10				
	Appartment Beside Road (LHS)													
	0.00	180.00		1	180.00			5.81		1044.90				
	UGD Cut Portion													
	Maruthi Farm 8th Cross Road													
	0.00	138.00		1	138.00			1.50		207.00				
	Coffee Board Layout													
	Road Portion													
	Bad Reaches													
	5th Cross Road													
				1	1.80			2.00		3.60				
				1	1.90			2.30		4.37				
				1	1.50			1.80		2.70				
				1	2.00			1.30		2.60				
				1	2.10			1.50		3.15				
				1	2.20			1.00		2.20				
				1	1.80			1.60		2.88				
	6th Cross Road													
				1	1.30			1.20		1.56				
				1	1.20			1.00		1.20				
	7th Cross Road													
				1	1.20			1.30		1.56				
				1	1.80			1.10		1.98				
	8th Cross Road													
				1	1.50			1.50		2.25				
				1	1.80			1.80		3.24				
				1	1.30			2.00		2.60				
				1	1.80			1.50		2.70				
				1	1.50			2.00		3.00				
				1	1.10			1.30		1.43				
	Kuvempu road(raghvendra circle to coffee board layout main road)													
				1	2.00			1.30		2.60				
				1	1.80			2.00		3.60				
				1	1.50			2.50		3.75				
				1	1.20			2.30		2.76				
				1	1.30			2.20		2.86				
				1	1.50			2.10		3.15				
				1	2.00			2.00		4.00				
				1	2.00			1.85		3.70				
				1	2.50			1.90		4.75				
				1	1.80			2.00		3.60				
				1	1.90			2.30		4.37				
				1	1.50			2.00		3.00				
				1	2.00			1.30		2.60				
				1	2.10			1.50		3.15				
				1	2.20			2.30		5.06				
				1	2.30			2.80		6.44				
				1	2.80			2.40		6.72				
				1	1.50			2.30		3.45				
				1	1.80			2.20		3.96				
				1	2.80			2.00		5.60				
				1	3.00			1.85		5.55				
				1	2.30			2.00		4.60				
				1	2.60			2.00		5.20				
	Coffe Board Zroad from green trends up to kannada flag													
				1	3.10			2.15		6.67				
				1	2.80			2.50		7.00				
				1	2.75			2.35		6.46				
				1	3.00			2.20		6.60				
				1	2.80			2.25		6.30				
				1	2.75			2.80		7.70				
				1	2.35			2.35		5.52				
				1	2.15			2.50		5.38				
				1	3.50			2.50		8.75				
				1	3.00			2.65		7.95				
	kannada flag to Main Road													
				1	1.30			2.10		2.73				
				1	2.30			2.35		5.41				
				1	2.50			2.40		6.00				
				1	2.20			2.50		5.50				

BQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
Hoysala Layout												
1st Cross Road												
0.00	317.30		1	317.30			4.72		1497.34			
2nd Cross Road												
0.00	83.50		1	83.50			3.71		309.87			
3rd Cross Road												
0.00	55.50		1	55.50			4.67		259.07			
4th Cross Road												
0.00	34.00		1	34.00			5.76		195.74			
5th Cross Road												
0.00	53.00		1	53.00			4.53		240.09			
6th Cross Road												
0.00	32.00		1	32.00			5.65		180.90			
7th Cross Road												
0.00	64.30		1	64.30			5.03		323.43			
18th c/s to JNC circle												
ORTUR Apartment Road												
0.00	628.00		1	628.00			2.02		1270.44			
0.00	628.00		1	628.00			1.66		1042.48			
Approachs												
			1	6.00			1.35		8.10			
			1	2.20			2.70		5.94			
			1	5.50			1.80		9.90			
			1	8.10			1.90		15.39			
			1	3.80			1.80		6.84			
			1	3.90			1.30		5.07			
			1	3.50			5.00		17.50			
			1	2.10			3.30		6.93			
			1	6.70			0.45		3.02			
Viensa Lake View Appatament Parrallel Road												
0.00	54.50		1	54.50			7.58		413.06			
Jakkur Double Rd												
19th Cross Road												
0.00	177.90		1	177.90			6.56		1167.11			
Approach Road												
0.00	52.30		1	52.30			7.21		377.14			
19th A Cross Road												
0.00	138.80		1	138.80			4.56		632.23			
Kuvempu Rd												
Road Cut Portion												
3rd Cross Road (Super Market Road)												
Road Edge												
Kuvempu Road												
0.00	256.00		1	256.00			0.94		239.36			
0.00	256.00		1	256.00			1.36		348.93			
Gopalappa to Cof Board												
Road Work												
St Antony Church Road												
(From Coffe Board Layout Park End)												
0.00	587.50		1	587.50			7.50		4403.90			
Cross Road St Antony Charch Road												
0.00	142.50		1	142.50			6.40		912.29			
Mandi Mariyappa Rd												
7th Cross Road (Mandi Mariyappa Palya)												
0.00	27.00		1	27.00			3.58		96.66			
Road Cut Portion												

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	Sahakar Nagar 60ft Road (Big Market Road)											
	0.00	810.00	1	810.00			12.53		10146.87			
	SAHAKARNAGAR 'A' BLOCK 15TH MAIN											
	0.00	203.00	1	203.00			8.32		1688.96			
	SAHAKARNAGAR 3RD MAIN G Block											
	0.00	135.00	1	135.00			5.84		788.27			
	Deduct Prime Coat (For UGD Cut Portion)								-3398.36			
	Big Market Sahakarnagar 60ft											
	15th Main Road											
	0.00	77.50	1	77.50			4.86		376.65			
	15th Cross Road											
	0.00	217.50	1	217.50			6.69		1454.42			
	16th Cross Road											
	0.00	193.20	1	193.20			8.09		1563.57			
	16th main Road											
	0.00	214.50	1	214.50			7.02		1505.15			
	17th Main Road											
	0.00	198.00	1	198.00			4.86		962.68			
	18th Main Road											
	0.00	151.10	1	151.10			7.41		1118.97			
	18th Cross Road											
	0.00	137.60	1	137.60			7.50		1031.59			
	19th main Road											
	0.00	148.00	1	148.00			7.11		1052.28			
	19th Cross Road											
	0.00	110.00	1	110.00			7.37		810.92			
	19th A Cross Road											
	0.00	94.70	1	94.70			7.55		714.51			
	20th main Road											
	0.00	78.50	1	78.50			4.89		384.10			
	20th Cross Road											
	0.00	85.50	1	85.50			9.39		803.19			
	21st Main Road											
	0.00	43.60	1	43.60			6.90		300.62			
	Happy Childhood Road											
	0.00	86.00	1	86.00			5.61		482.46			
	Deductions of Prime Coat								Qty vide item	-2403.19		
	Pampa Extension Road											
	Pampa											
	1st Cross											
	0.00	39.90	1	39.90			4.63		184.54			
	2nd											
	0.00	29.80	1	29.80			4.95		147.51			
	3rd Cross											
	0.00	24.10	1	24.10			4.00		96.40			
	4th Cross											
	0.00	66.00	1	66.00			5.28		348.61			
	9th Cross											
	0.00	92.70	1	92.70			5.37		497.80			
	11th											
	0.00	69.50	1	69.50			5.91		410.54			
	12th											
	0.00	126.10	1	126.10			5.51		694.31			
	2nd Main											
	0.00	68.60	1	68.60			3.25		222.95			
	3rd Main											
	0.00	131.60	1	131.60			3.63		477.58			
	4th Main											
	0.00	236.70	1	236.70			5.08		1203.15			
	5th Main											
	0.00	241.10	1	241.10			4.49		1082.30			
	2nd Main											
	0.00	99.20	1	99.20			5.13		509.19			
	1st C											
	0.00	10.80	1	10.80			5.10		55.08			
	1st B											
	0.00	35.10	1	35.10			3.41		119.66			
	1st A											
	0.00	35.10	1	35.10			3.74		131.27			
	Deduct Prime Coat								-101.28			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
20th Main Road (bescom)													
	0.00	74.00		1	74.00			4.83	0.23	82.12			
21st Main Road													
				1	0.30			7.00	0.23	0.48			
20th Cross Road													
				1	0.20			8.50	0.23	0.39			
				1	0.30			9.00	0.23	0.62			
				1	0.25			10.60	0.23	0.61			
Edge Lines													
	0.00	85.50		1	85.50			1.00	0.23	19.67			
Happy Childhood Road													
				1	4.00			1.50	0.23	1.38			
				1	0.30			5.60	0.23	0.39			
Edge Lines													
	0.00	95.20		1	95.20			1.43	0.23	31.31			
	0.00	95.20		1	95.20			1.42	0.23	31.14			
Ayyappa Swamy Temple Road													
5th Cross Road													
				1	31.00			5.83	0.23	41.60			
Cubic Apartment													
1st Main Road													
	0.00	177.00		1	177.00			10.33	0.23	420.53			
Connecting Road From 1st Mn to 2nd Main Road													
	0.00	26.40		1	26.40			7.70	0.23	46.75			
2nd Main Road													
	0.00	209.20		1	209.20			9.58	0.23	460.71			
1st Cross Road													
	0.00	46.30		1	46.30			6.52	0.23	69.38			
Cubic Apartment													
2nd Cross Road													
	0.00	44.90		1	44.90			5.48	0.23	56.62			
3rd Cross Road													
	0.00	44.60		1	44.60			5.60	0.23	57.44			
4th Cross Road													
	0.00	44.00		1	44.00			4.36	0.23	44.14			
Pampa Extension Road													
Road Portion													
Bad Reaches													
Pampa Extension													
1st Cross Road													
				1	1.80			1.50	0.23	0.62			
				1	1.50			1.40	0.23	0.48			
2nd Cross Road													
				1	1.30			1.50	0.23	0.45			
3rd Cross Road													
				1	1.50			1.00	0.23	0.35			
4th Cross Road													
				1	1.50			1.30	0.23	0.45			
				1	1.10			1.20	0.23	0.30			
				1	1.50			1.10	0.23	0.38			
9th Cross Road													
				1	2.00			1.30	0.23	0.60			
				1	1.20			1.20	0.23	0.33			
				1	1.00			1.10	0.23	0.25			
				1	1.30			1.20	0.23	0.36			
11th Cross Road													
				1	1.80			1.70	0.23	0.70			
				1	1.50			1.25	0.23	0.43			
				1	1.15			1.30	0.23	0.34			
12th Cross Road													

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	1st Cross rd (2nd Main Rd)											
	0.00 48.70		1	48.70			4.68		227.77			
	3rd Cross rd (2nd Main Rd)											
	0.00 120.00		1	120.00			5.74		688.56			
	4th Cross rd (2nd Main Rd- 1st Main rd)											
	0.00 109.30		1	109.30			5.75		628.15			
	5th Cross rd (2nd Main Rd- 1st Main rd)											
	0.00 104.30		1	104.30			6.03		628.93			
	5th Cross rd in Cross Rd 1											
	0.00 25.00		1	25.00			4.25		106.25			
	5th Cross rd in Cross Rd 2											
	0.00 55.00		1	55.00			6.81		374.55			
	6th Cross rd (2nd Main Rd)											
	0.00 39.80		1	39.80			4.31		171.54			
	7th Cross rd (2nd Main Rd)											
	0.00 40.30		1	40.30			5.58		224.87			
	1st Cross rd Maruthi Farm											
	0.00 25.90		1.00	25.90			4.25		110.08			
	2nd Cross rd Maruthi Farm											
	0.00 32.50		1.00	32.50			4.80		156.00			
	3rd Cross rd Maruthi Farm											
	0.00 38.50		1	38.50			4.22		162.39			
	4th Cross rd Maruthi Farm											
	0.00 44.30		1	44.30			4.49		199.00			
	Muniramayya Layout											
	0.00 48.00		1	48.00			3.26		156.62			
	5th A cross Road											
	0.00 62.70		1	62.70			5.30		332.25			
	7th cross Road 1st Main rd											
	0.00 60.50		1	60.50			6.23		376.79			
	7th A cross Road 1st Main rd											
	0.00 34.70		1	34.70			5.82		201.95			
	6th cross Road 1st Main rd											
	0.00 83.20		1	83.20			5.62		467.58			
	1st cross Road C Sector											
	0.00 52.90		1	52.90			6.30		333.01			
							Deduct Prime Coat		-2233.34			
	Talakaveri Layout											
	5th Cross Road											
	0.00 120.00		1	120.00			8.54		1024.80			
	6th Cross Road											
	0.00 191.00		1	191.00			7.97		1522.84			
	6th A Cross Road											
	0.00 138.20		1	138.20			6.40		884.34			
	7th A Cross Road											
	0.00 149.60		1	149.60			8.62		1289.70			
	7th Cross Road											
	0.00 222.10		1	222.10			7.34		1630.21			
	2nd A Main Road											
	0.00 90.10		1	90.10			6.23		561.68			
	3rd Main Road											
	0.00 270.00		1	270.00			7.95		2145.15			
	Coffe Board Layout											
	5th Cross Road											
	0.00 179.00		1	179.00			5.07		908.07			
	6th Cross Road											
	0.00 39.80		1	39.80			5.67		225.67			
	7th Cross Road											
	0.00 50.00		1	50.00			5.63		281.50			
	8th Cross Road											
	0.00 145.00		1	145.00			6.19		896.97			
	Kuvempu road(raghvendra circle to coffee board layout main road)											
	0.00 670.20		1	670.20			7.48		5015.11			
	Coffe Board Zroad from green trends up to kannada flag											

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	Connected to 1st c/s Venkatappa Badavane											
	0.00	36.70	1	36.70			3.80		139.46			
	Venkatappa Badavane 2nd c/s Rd											
	0.00	73.00	1	73.00			3.30		240.90			
	Venkatappa Badavane 3rd c/s Rd											
	0.00	45.00	1	45.00			3.40		153.00			
	MLA CB Krishne Byeregowda House Rd											
	0.00	286.00	1	282.90			7.80		2,206.62			
	From Shanthivana Rd end at Sardar Vallabhbhai Patel											
	0.00	401.50	1	401.50			9.10		3,653.65			
	Connecting Rd from Shanthivana Rd to CB Krishna Byeregowda											
	0.00	130.20	1	127.20			9.00		1,144.80			
							Deduction of Prime Coat (-)					
							Kempapura Main Road					
									-2841.42			
							Total Quantity		90552.09	Sqm	3.4	307877.11
28	KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH / Chapter 5 (P.No.161 I.No.21.7 of PW,P&IWD SR of 2016-17)											
	Big Market Sahakarnagar 60ft											
	Sahakar Nagar 60ft Road (Big Market Road)											
	0.00	810.00	1	810.00			12.53		10146.87			
	SAHAKARNAGAR 'A' BLOCK 15TH MAIN											
	0.00	203.00	1.00	203.00			8.32		1688.96			
	SAHAKARNAGAR 3RD MAIN G Block											
	0.00	135.00	1.00	135.00			5.84		788.27			
	Big Market Sahakarnagar 60ft											
	Sahakaranagar											
	15th Main Road											
			1	0.40			4.55		1.82			
	Edge Lines											
	LHS											
	15.00	45.00	1	30.00			0.90		27.00			
	15th Cross Road											
			2	0.80			2.40		3.84			
			3	1.70			0.70		3.57			
			1	0.80			0.70		0.56			
	Edge Lines											
	LHS											
			1	65.80			1.22		80.14			
			1	0.50			1.15		0.58			
	16 th Cross Road											
	Bad Reaches											
	0.00	28.00	1	28.00			8.57		239.96			
	16th Main Road											
			1	0.20			0.30		0.06			
			1	0.70			4.40		3.08			
			1	0.20			4.60		0.92			
	Edge Lines											
	LHS											
			L/S	1	15.00		0.40		6.00			
			L/S	1	14.20		0.40		5.68			

Modified Estimate

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
											Rs.	Rs.	
		L/S	1	15.00			0.35		5.25				
		L/S	1	15.00			0.35		5.25				
		L/S	1	15.00			0.55		8.25				
		L/S	1	15.00			0.55		8.25				
		L/S	1	15.00			0.85		12.75				
		L/S	1	15.00			0.85		12.75				
	RHS												
		R/S	1	15.00			0.45		6.75				
		R/S	1	14.20			0.45		6.39				
		R/S	1	15.00			0.40		6.00				
		R/S	1	15.00			0.40		6.00				
		R/S	1	15.00			0.40		6.00				
		R/S	1	16.20			0.40		6.48				
		R/S	1	15.00			0.35		5.25				
		R/S	1	15.00			0.35		5.25				
		R/S	1	6.80			0.35		2.38				
		R/S	1	15.00			0.40		6.00				
		R/S	1	8.20			0.40		3.28				
		R/S	1	15.00			0.30		4.50				
	17th Main Road												
			1	1.00			0.80		0.80				
			1	0.30			3.40		1.02				
			1	2.90			0.40		1.16				
			1	0.30			3.60		1.08				
			1	0.40			0.40		0.16				
			1	0.20			5.20		1.04				
			1	0.30			3.80		1.14				
			1	1.20			0.30		0.36				
	Edge Lines												
	LHS												
		L/S	1	13.10			0.65		8.52				
		L/S	1	15.00			0.60		9.00				
		L/S	1	15.00			0.60		9.00				
		L/S	1	9.70			0.60		5.82				
		L/S	1	15.00			0.60		9.00				
		L/S	1	15.00			0.60		9.00				
		L/S	1	15.00			0.60		9.00				
		L/S	1	4.80			0.60		2.88				
	RHS												
		R/S	1	15.00			0.25		3.75				
		R/S	1	4.00			0.25		1.00				
		R/S	1	13.40			0.40		5.36				
		R/S	1	3.20			0.30		0.96				
		R/S	1	15.00			0.25		3.75				
		R/S	1	11.80			0.25		2.95				
		R/S	1	15.00			0.45		6.75				
		R/S	1	15.00			0.45		6.75				
	18th Main Road												
			1	0.80			0.90		0.72				
			1	5.10			0.50		2.55				
			1	5.20			0.50		2.60				
			1	2.60			2.10		5.46				
	Edge Lines												
	LHS												
		L/S	1	10.80			0.90		9.72				
		L/S	1	15.00			0.55		8.25				
		L/S	1	15.00			0.55		8.25				
		L/S	1	10.00			0.55		5.50				
	RHS												
		R/S	1	15.00			1.05		15.75				
		R/S	1	15.00			1.05		15.75				
		R/S	1	9.90			1.05		10.40				
		R/S	1	15.00			0.75		11.25				

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
		R/S	1	15.00			0.75		11.25			
		R/S	1	3.70			0.75		2.78			
		R/S	1	15.00			0.45		6.75			
	18th Cross Road											
			1	1.00			0.80		0.80			
			1	0.80			1.20		0.96			
			1	0.30			6.50		1.95			
			1	4.50			2.90		13.05			
	Edge Lines											
	LHS											
		L/S	1	15.00			1.35		20.25			
		L/S	1	15.00			1.35		20.25			
	19th Main Road											
			1	0.80			1.20		0.96			
			1	1.50			1.00		1.50			
		L/S	1	6.00			1.00		6.00			
	RHS											
		R/S	1	15.00			1.08		16.13			
		R/S	1	13.10			1.08		14.08			
		R/S	1	9.70			1.19		11.52			
		R/S	1	2.40			1.24		2.99			
	19th Cross Road											
			1	0.40			0.30		0.12			
			1	0.30			6.20		1.86			
			1	1.30			0.40		0.52			
			1	5.40			0.40		2.16			
			1	0.30			1.60		0.48			
	Edge Lines											
	LHS											
		L/S	1	14.70			0.25		3.68			
		L/S	1	14.90			0.30		4.47			
		L/S	1	10.70			0.30		3.21			
	RHS											
		R/S	1	15.00			0.70		10.50			
		R/S	1	4.40			0.70		3.08			
		R/S	1	7.70			0.20		1.54			
	19th A Cross Road											
			1	1.20			2.00		2.40			
	Edge Lines											
	LHS											
		L/S	1	15.00			0.35		5.25			
		L/S	1	11.00			0.35		3.85			
		L/S	1	15.00			0.40		6.00			
		L/S	1	15.30			0.40		6.12			
		L/S	1	15.00			1.00		15.00			
		L/S	1	11.10			1.00		11.10			
	RHS											
		R/S	1	4.30			0.30		1.29			
		R/S	1	15.00			0.30		4.50			
		R/S	1	7.10			0.30		2.13			
		R/S	1	14.70			0.25		3.68			
	20th Main Road (bescom)											
	5.00 15.00		1	10.00			4.35		43.50			
	20th Cross Road											
			1	0.20			8.50		1.70			
			1	0.30			9.00		2.70			
	21st Main Road											
			1	0.30			7.00		2.10			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	4th Main Road											
	0.00 236.70		1	236.70			5.08		1203.15			
	5th Main Road											
	0.00 241.10		1	241.10			4.49		1082.30			
	2nd Main Road (durgaparameshwari Temple Road)											
	0.00 99.20		1	99.20			5.13		509.19			
	1st C Cross (KVJ Road)											
	0.00 10.80		1	10.80			5.10		55.08			
	1st B Cross (KVJ Road)											
	0.00 35.10		1	35.10			3.41		119.66			
	1st A Cross (KVJ Road)											
	0.00 35.10		1	35.10			3.74		131.27			
	Pampa Extension Road											
	For DBM											
	Vinayaka layout											
	Bad Reaches											
			1	3.20			0.40		1.28			
			1	2.00			1.10		2.20			
	1st B Cross Road											
			1	15.00			0.90		13.50			
			1	6.00			0.90		5.40			
	2nd B Cross Road											
			1	1.10			1.20		1.32			
			1	1.00			2.90		2.90			
	3rd Cross Road											
	LHS											
			1	12.10			0.30		3.63			
	4th A Cross Road											
	Edge Lines											
	LHS											
		L/S	1	4.40			0.20		0.88			
	RHS											
		R/S	1	10.40			0.40		4.16			
	5th Cross Road											
	15.00 30.00		1	15.00			5.93		88.88			
	6th Cross Road											
	30.00 45.00		1	15.00			5.95		89.25			
	Kempapura											
	1st Cross Road											
	20.00 30.00		1	10.00			3.90		39.00			
	2nd Cross Road											
			1	1.15			4.80		5.52			
	Edge Lines											
	RHS											
		R/S	1	15.00			0.55		8.25			
	3rd Cross Road											
			1	6.00			3.40		20.40			
	Pampa Extension Road											
	Vinayaka Layout											
	1st Main Road											
	0.00 163.50		1	163.50			4.07		665.45			
	1st B Cross Road											
	0.00 64.40		1	64.40			6.11		393.48			
	2nd B Cross Road											
	0.00 81.00		1	81.00			6.00		486.00			
	3rd Cross Road											
	0.00 76.60		1	76.60			5.12		392.04			

Modified Estimate

Modified Estimate														Rate	Amount
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rs.	Rs.		
	Chainage											Rs.	Rs.		
	4th A Cross Road														
	0.00	73.00		1	73.00			5.98		436.25					
	5th Cross Road														
	0.00	47.50		1	47.50			6.01		285.62					
	6th Cross Road														
	0.00	47.50		1	47.50			6.15		292.32					
	Kempapura														
	1st Cross Road														
	0.00	39.00		1	39.00			3.95		154.05					
	2nd Cross Road														
	0.00	38.70		1	38.70			3.58		138.66					
	3rd Cross Road														
	0.00	37.80		1	37.80			3.73		141.07					
	4th Cross Road														
	0.00	39.50		1	39.50			4.53		178.97					
	Cubic Apartment														
	1st Main Road														
	0.00	177.00		1	177.00			10.33		1828.41					
	Connecting Road From 1st Mn to 2nd Main Road														
	0.00	26.40		1	26.40			7.70		203.28					
	2nd Main Road														
	0.00	209.20		1	209.20			9.58		2003.30					
	1st Cross Road														
	0.00	46.30		1	46.30			6.52		301.64					
	2nd Cross Road														
	0.00	44.90		1	44.90			5.48		246.23					
	3rd Cross Road														
	0.00	44.60		1	44.60			5.60		249.67					
	4th Cross Road														
	0.00	44.00		1	44.00			4.37		192.24					
	Amruth nagar A Sector														
	1st Main Road														
	LHS														
	0.00	452.70		1	452.70			9.14		4135.87					
	2nd Main Road in 1st Cross Road														
	0.00	100.60		1	100.60			6.34		638.21					
	1st A Cross Road														
	0.00	12.00		1	12.00			5.90		70.80					
	1st Cross Road Block B Apartment														
	0.00	19.30		1	19.30			4.85		93.61					
	Sri Sai Sannidi Apartment Road Amruthnagar														
	Road B/W 1st cr & 2nd Cross rd														
	0.00	42.00		1	42.00			4.44		186.31					
	Road B/W 2nd Cross & 3rd Cross rd														
	0.00	31.00		1	31.00			5.60		173.60					
	Road B/W 3rd Cross & 4th Cross rd														
	0.00	30.80		1	30.80			6.40		197.12					
	Road B/W 4th Cross & 5th Cross														
	0.00	27.00		1	27.00			6.95		187.65					
	2nd Cross Road														
	0.00	199.60		1	199.60			5.43		1083.83					
	3rd Cross Road														
	0.00	114.60		1	114.60			5.73		656.09					
	4th Cross Road														
	0.00	173.30		1	173.30			5.54		960.43					
	5th Cross Road														
	0.00	130.00		1	130.00			5.81		755.56					
	2nd B Cross Road														
	0.00	87.60		1	87.60			4.89		428.63					

BOQ Item No

Description

Side

Nos

L

B1

B2

Avg width

Depth

Quantity

Unit

Rate

Amount

Chainage

Rs.

Rs.

1st Main Road Beside BBMP Park												
	0.00	279.50	1	279.50			6.17		1724.52			
2nd Main Road												
	0.00	298.50	1	298.50			5.70		1702.05			
8th Cross Road												
	0.00	86.00	1	86.00			6.29		540.85			
8th A Cross Road												
	0.00	38.20	1	38.20			5.56		212.39			
1st Cross rd (2nd Main Rd)												
	0.00	48.70	1	48.70			4.68		227.77			
3rd Cross rd (2nd Main Rd)												
	0.00	120.00	1	120.00			5.74		688.56			
4th Cross rd (2nd Main Rd- 1st Main rd)												
	0.00	109.30	1	109.30			5.75		628.15			
5th Cross rd (2nd Main Rd- 1st Main rd)												
	0.00	104.30	1	104.30			6.03		628.93			
5th Cross rd in Cross Rd 1												
	0.00	25.00	1	25.00			4.25		106.25			
5th Cross rd in Cross Rd 2												
	0.00	55.00	1	55.00			6.81		374.55			
6th Cross rd (2nd Main Rd)												
	0.00	39.80	1	39.80			4.31		171.54			
7th Cross rd (2nd Main Rd)												
	0.00	40.30	1	40.30			5.58		224.87			
1st Cross rd Maruthi Farm												
	0.00	25.90	1	25.90			4.25		110.08			
2nd Cross rd Maruthi Farm												
	0.00	32.50	1	32.50			4.80		156.00			
3rd Cross rd Maruthi Farm												
	0.00	38.50	1	38.50			4.22		162.39			
4th Cross rd Maruthi Farm												
	0.00	44.30	1	44.30			4.49		199.00			
Muniramayya Layout												
	0.00	48.00	1	48.00			3.26		156.62			
5th A cross Road												
	0.00	62.70	1	62.70			5.30		332.25			
7th cross Road 1st Main rd												
	0.00	60.50	1	60.50			6.23		376.79			
7th A cross Road 1st Main rd												
	0.00	34.70	1	34.70			5.82		201.95			
6th cross Road 1st Main rd												
	0.00	83.20	1	83.20			5.62		467.58			
1st cross Road C Sector												
	0.00	52.90	1	52.90			6.30		333.01			
Talakaveri Layout												
5th Cross Road												
	0.00	120.00	1	120.00			8.54		1024.80			
6th Cross Road												
	0.00	191.00	1	191.00			7.97		1522.84			
6th A Cross Road												
	0.00	138.20	1	138.20			6.40		884.34			
7th A Cross Road												
	0.00	149.60	1	149.60			8.62		1289.70			
7th Cross Road												
	0.00	222.10	1	222.10			7.34		1630.21			
2nd A Main Road												
	0.00	90.10	1	90.10			6.23		561.68			
3rd Main Road												
	0.00	270.00	1	270.00			7.95		2145.15			
Coffe Board Layout												
5th Cross Road												
	0.00	179.00	1	179.00			5.07		908.07			
6th Cross Road												
	0.00	39.80	1	39.80			5.67		225.67			
7th Cross Road												
	0.00	50.00	1	50.00			5.63		281.50			
8th Cross Road												
	0.00	145.00	1	145.00			6.19		896.97			
Kuvempu road(raghvendra circle to coffee board layout main road)												
	0.00	670.20	1	670.20			7.48		5015.11			
Coffe Board Zroad from green trends up to kannada flag												

Page 69 of 102

Modified Estimate

Modified Estimate													
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	Happy Childhood Road												
				1	4.00			1.50		6.00			
	Edge Lines												
	RHS												
			R/S	1	15.00			1.40		21.00			
	Ayyappa Swamy Temple Road												
	5th Cross Road												
	0.00	234.00		1	234.00			8.63		2019.89			
	For BC												
	Big Market Sahakarnagar 60ft												
	15th Main Road												
	0.00	77.50		1	77.50			4.86		376.65			
	15th Cross Road												
	0.00	217.50		1	217.50			6.69		1454.42			
	16th Cross Road												
	0.00	193.20		1	193.20			8.09		1563.57			
	16th main Road												
	0.00	214.50		1	214.50			7.02		1505.15			
	17th Main Road												
	0.00	198.00		1	198.00			4.86		962.68			
	18th Main Road												
	0.00	151.10		1	151.10			7.41		1118.97			
	18th Cross Road												
	0.00	137.60		1	137.60			7.50		1031.59			
	19th main Road												
	0.00	148.00		1	148.00			7.11		1052.28			
	19th Cross Road												
	0.00	110.00		1	110.00			7.37		810.92			
	19th A Cross Road												
	0.00	94.70		1	94.70			7.55		714.51			
	20th main Road												
	0.00	78.50		1	78.50			4.89		384.10			
	20th Cross Road												
	0.00	85.50		1	85.50			9.39		803.19			
	21st Main Road												
	0.00	43.60		1	43.60			6.90		300.62			
	Happy Childhood Road												
	0.00	86.00		1	86.00			5.61		482.46			
	Ayyappa Swamy Temple Road												
	5th Cross Road												
	0.00	234.00		1	234.00			8.63		2019.89			
	Pampa Extension Road												
	Pampa Extension												
	1st Cross Road												
	0.00	39.90		1	39.90			4.63		184.54			
	2nd Cross Road												
	0.00	29.80		1	29.80			4.95		147.51			
	3rd Cross Road												
	0.00	24.10		1	24.10			4.00		96.40			
	4th Cross Road												
	0.00	66.00		1	66.00			5.28		348.61			
	9th Cross Road												
	0.00	92.70		1	92.70			5.37		497.80			
	11th Cross Road												
	0.00	69.50		1	69.50			5.91		410.54			
	12th Cross Road												
	0.00	126.10		1	126.10			5.51		694.31			
	2nd Main Road												
	0.00	68.60		1	68.60			3.25		222.95			
	3rd Main Road												
	0.00	131.60		1	131.60			3.63		477.58			

Modified Estimate														
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
	Chainage											Rs.	Rs.	
	0.00	265.40		1	265.40			5.99		1590.54				
	kannada flag to Main Road													
	0.00	115.00		1	115.00			6.86		788.79				
	Hoysala Layout													
	1st Cross Road													
	0.00	317.30		1	317.30			4.72		1497.34				
	2nd Cross Road													
	0.00	83.50		1	83.50			3.71		309.87				
	3rd Cross Road													
	0.00	55.50		1	55.50			4.67		259.07				
	4th Cross Road													
	0.00	34.00		1	34.00			5.76		195.74				
	5th Cross Road													
	0.00	53.00		1	53.00			4.53		240.09				
	6th Cross Road													
	0.00	32.00		1	32.00			5.65		180.90				
	7th Cross Road													
	0.00	64.30		1	64.30			5.03		323.43				
	18th c/s to JNC circle													
	Tack coat fr BC													
	ORPUR Apartment Road (Amruthhalli to Dasarahalli Main Road)--Road.													
	0.00	626.00		1	624.80			9.17		5730.67				
	Approachs													
				1	6.00			1.35		8.10				
				1	2.20			2.70		5.94				
				1	5.50			1.80		9.90				
				1	8.10			1.90		15.39				
				1	3.80			1.80		6.84				
				1	3.90			1.30		5.07				
				1	3.50			5.00		17.50				
				1	2.10			3.30		6.93				
				1	6.70			0.45		3.02				
	Janatha Colony Road (Road)													
	0.00	38.80		1	38.80			5.61		217.67				
	Viensa Lake View Appatament Parrallel Road													
	0.00	54.50		1	54.50			7.58		413.06				
	Jakkur Double Rd													
	Tack Coat for BC													
	Jakkur Layout													
	13th A Cross Road													
	0.00	84.00		1	84.00			6.08		510.72				
	Ramp Asphalt 5*1.2			1	5.00			1.20		6.00				
	14th A Cross Road													
	0.00	68.00		1	68.00			5.98		406.64				
	Ramp Asphalt 7.3*2			1	7.30			2.00		14.60				
	15th A Cross Road													
	0.00	218.50		1	218.50			7.82		1709.11				
	Ramp Asphalt 7.3*2			1	7.30			2.00		14.60				
	Hoysala samruddhi Appartments Road Opposite to 15th Cross A Road													
	0.00	47.30		1	47.30			5.06		239.34				
	Talakaveri Badavane 8th Cross Road													
	0.00	144.70		1	144.70			8.03		1162.09				
	16th A Cross Road													
	0.00	125.10		1	125.10			5.56		695.18				
	17th A Cross Road													
	0.00	27.50		1	27.50			5.79		159.31				
	Approach			1	1.50			5.00		7.50				
	18th A Cross Road													
	0.00	46.00		1	46.00			4.68		215.05				

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	Approach Road												
	0.00	100.50		1	100.50			4.96		498.58			
	Jakkur Double Rd												
	19th Cross Road												
	0.00	177.90		1	177.90			6.56		1167.11			
	Approach Road												
	0.00	52.30		1	52.30			7.21		377.14			
	19th A Cross Road												
	0.00	138.80		1	138.80			4.56		632.23			
	Kuvempu Rd												
	Road Cut Portion												
	3rd Cross Road (Super Market Road)												
	Road Edge												
	Kuvempu Road												
	0.00	256.00	L/S	1	256.00			0.94		239.36			
	0.00	256.00	R/S	1	256.00			1.36		348.93			
	Tack Coat for BC												
	Kuvempu Road Coffe Board Layout (Road)												
	0.00	256.00		1	256.00			7.62		1951.23			
	Gopalappa to Cof Board												
	Tack Coat for DBM												
	St Antony Chaurch Road												
	(From Coffe Board Layout Park End)												
	0.00	587.50		1	587.50			7.50		4403.90			
	Cross Road St Antony Charch Road												
	0.00	142.50		1	142.50			6.40		912.29			
	Tack Coat for BC												
	St Antony Chaurch Road												
	(From Coffe Board Layout Park End)												
	0.00	587.50		1	587.50			7.50		4403.90			
	Cross Road St Antony Charch Road												
	0.00	142.50		1	142.50			6.40		912.29			
	Mandi Mariyappa Rd												
	Tack Coat for DBM												
	7th Cross Road (Mandi Mariyappa Palya)												
	0.00	27.00		1	27.00			3.58		96.66			
	Road Cut Portion												
	3rd Main Road (Mandi Mariyappa Reddy Road)												
	0.00	802.80		1	802.80			4.52		3624.64			
	Tack Coat for BC												
	7th Cross Road (Mandi Mariyappa Palya)												
	0.00	27.00		1	27.00			3.58		96.66			
	Road Cut Portion												
	3rd Main Road (Mandi Mariyappa Reddy Road)												
	0.00	772.50		1	772.50			8.00		6180.00			
	3rd Main Road Mariyanna Palya Continue From (Himagiri Complex)- Road												
	0.00	225.00		1	225.00			7.00		1575.00			
	Tack Coat For DBM												
	Kempapura Main Road												
	410.00	515.00		1	105.00			8.40		882.00			
	Tack Coat For BC												
	Jain School Road												
	0.00	38.10		1	38.10			6.29		239.65			
	Kempapura Main Road												
	0.00	146.00		1	144.80			5.28		764.54			
	146.00	700.00		1	554.00			9.70		5,373.80			

Modified Estimate

Modified Estimate													
BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	Vidyanikethan School Road												
	0.00	42.00		1	42.00			7.50		315.00			
	Sindhi College Gate												
	0.00	277.00		1	277.00			5.20		1,440.40			
	Venkatappa Badavane 1st c/s Rd												
	0.00	70.80		1	70.80			3.50		247.80			
	Connected to 1st c/s Venkatappa Badavane												
	0.00	36.70		1	36.70			3.80		139.46			
	Venkatappa Badavane 2nd c/s Rd												
	0.00	73.00		1	73.00			3.30		240.90			
	Venkatappa Badavane 3rd c/s Rd												
	0.00	45.00		1	45.00			3.40		153.00			
	Heera Caters Rd (Mariyappanapalya)												
	0.00	79.00		1	79.00			6.40		505.60			
	MLA CB Krishne Byeregowda House Rd												
	0.00	286.00		1	282.90			7.80		2,206.62			
	From Shanthivana Rd end at Sardar Vallabhbhai Patel												
	0.00	401.50		1	401.50			9.10		3,653.65			
	Connecting Rd from Shanthivana Rd to CB Krishna Byeregowda												
	0.00	130.20		1	127.20			9.00		1,144.80			

Modified Estimate

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.	BOQ No
			1	15.00			0.75	0.05	0.56				
			1	15.00			0.75	0.05	0.56				
			1	3.70			0.75	0.05	0.14				
			1	15.00			0.45	0.05	0.34				
	18th Cross Road												
			1	1.00			0.80	0.05	0.04				
			1	0.80			1.20	0.05	0.05				
			1	0.30			6.50	0.05	0.10				
			1	4.50			2.90	0.05	0.65				
	Edge Lines												
	LHS												
			1	15.00			1.35	0.05	1.01				
			1	15.00			1.35	0.05	1.01				
	19th Main Road												
			1	0.80			1.20	0.05	0.05				
			1	1.50			1.00	0.05	0.08				
			1	6.00			1.00	0.05	0.30				
	RHS												
			1	15.00			1.08	0.05	0.81				
			1	13.10			1.08	0.05	0.70				
			1	9.70			1.19	0.05	0.58				
			1	2.40			1.24	0.05	0.15				
	19th Cross Road												
			1	0.40			0.30	0.05	0.01				
			1	0.30			6.20	0.05	0.09				
			1	1.30			0.40	0.05	0.03				
			1	5.40			0.40	0.05	0.11				
			1	0.30			1.60	0.05	0.02				
	Edge Lines												
	LHS												
			1	14.70			0.25	0.05	0.18				
			1	14.90			0.30	0.05	0.22				
			1	10.70			0.30	0.05	0.16				
	RHS												
			1	15.00			0.70	0.05	0.53				
			1	4.40			0.70	0.05	0.15				
			1	7.70			0.20	0.05	0.08				
	19th A Cross Road												
			1	1.20			2.00	0.05	0.12				
	Edge Lines												
	LHS												
			1	15.00			0.35	0.05	0.26				
			1	11.00			0.35	0.05	0.19				
			1	15.00			0.40	0.05	0.30				
			1	15.30			0.40	0.05	0.31				
			1	15.00			1.00	0.05	0.75				
			1	11.10			1.00	0.05	0.56				
	RHS												
			1	4.30			0.30	0.05	0.06				
			1	15.00			0.30	0.05	0.23				
			1	7.10			0.30	0.05	0.11				
			1	14.70			0.25	0.05	0.18				
	20th Main Road (bescom)												
			1	10.00			4.35	0.05	2.18				
	20th Cross Road												
			1	0.20			8.50	0.05	0.09				
			1	0.30			9.00	0.05	0.14				
	21st Main Road												
			1	0.30			7.00	0.05	0.11				
	Happy Childhood Road												
			1	4.00			1.50	0.05	0.30				
	RHS												
			1	15.00			1.40	0.05	1.05				
	Ayyappa Swamy Temple Road												

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	5th Cross Road		1	234.00			8.63	0.05	100.99			
	Pampa Extension Road											
	For DBM											
	Vinayaka layout											
	Bad Reaches		1	3.20			0.40	0.05	0.06			
			1	2.00			1.10	0.05	0.11			
	1st B Cross Road		1	15.00			0.90	0.05	0.68			
			1	6.00			0.90	0.05	0.27			
	2nd B Cross Road		1	1.10			1.20	0.05	0.07			
			1	1.00			2.90	0.05	0.15			
	3rd Cross Road											
	LHS		1	12.10			0.30	0.05	0.18			
	4th A Cross Road											
	Edge Lines											
	LHS	L/S	1	4.40			0.20	0.05	0.04			
	RHS	R/S	1	10.40			0.40	0.05	0.21			
	5th Cross Road											
	15.00 30.00		1	15.00	6.00	5.85	5.93	0.05	4.44			
	6th Cross Road											
	30.00 45.00		1	15.00	6.00	5.90	5.95	0.05	4.46			
	Kempapura											
	1st Cross Road		1	10.00	4.00	3.80	3.90	0.05	1.95			
	20.00 30.00											
	2nd Cross Road		1	1.15	0.00		4.80	0.05	0.28			
	Edge Lines											
	RHS	R/S	1	15.00			0.55	0.05	0.41			
	3rd Cross Road		1	6.00			3.40	0.05	1.02			
	Kuvempu Rd											
	Road Cut Portion											
	3rd Cross Road (Super Market Road)											
	Road Edge											
	Kuvempu Road											
	0.00 256.00	L/S	1	256.00			0.94	0.05	11.97			
	0.00 256.00	R/S	1	256.00			1.36	0.05	17.45			
	Gopalappa to Cof Board											
	Tack Coat for DBM											
	St Antony Chaurch Road											
	(From Coffe Board Layout Park End)											
	0.00 587.50		1	587.50			7.50	0.05	220.20			
	Cross Road St Antony Charch Road											
	0.00 142.50		1	142.50			6.40	0.05	45.61			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	0.00	39.00	1	39.00			3.95	0.04	6.16			
	2nd Cross Road											
	0.00	38.70	1	38.70			3.58	0.04	5.55			
	3rd Cross Road											
	0.00	37.80	1	37.80			3.73	0.04	5.64			
	4th Cross Road											
	0.00	39.50	1	39.50			4.53	0.04	7.16			
	Cubic Apartment											
	1st Main Road											
	0.00	177.00	1	177.00			10.33	0.04	73.14			
	Connecting Road From 1st Mn to 2nd Main Road											
	0.00	26.40	1	26.40			7.70	0.04	8.13			
	2nd Main Road											
	0.00	209.20	1	209.20			9.58	0.04	80.13			
	1st Cross Road											
	0.00	46.30	1	46.30			6.52	0.04	12.07			
	2nd Cross Road											
	0.00	44.90	1	44.90			5.48	0.04	9.85			
	3rd Cross Road											
	0.00	44.60	1	44.60			5.60	0.04	9.99			
	4th Cross Road											
	0.00	44.00	1	44.00			4.37	0.04	7.69			
	Amruth nagar A Sector											
	1st Main Road											
	LHS											
	0.00	452.70	1	452.70			9.14	0.04	165.43			
	2nd Main Road in 1st Cross Road											
	0.00	100.60	1	100.60			6.34	0.04	25.53			
	1st A Cross Road											
	0.00	12.00	1	12.00			5.90	0.04	2.83			
	1st Cross Road Block B Apartment											
	0.00	19.30	1	19.30			4.85	0.04	3.74			
	Sri Sai Sannidi Apartment Road Amruthnagar											
	Road B/W 1st cr & 2nd Cross rd											
	0.00	42.00	1	42.00			4.44	0.04	7.45			
	Road B/W 2nd Cross & 3rd Cross rd											
	0.00	31.00	1	31.00			5.60	0.04	6.94			
	Road B/W 3rd Cross & 4th Cross rd											
	0.00	30.80	1	30.80			6.40	0.04	7.88			
	Road B/W 4th Cross & 5th Cross											
	0.00	27.00	1	27.00			6.95	0.04	7.51			
	2nd Cross Road											
	0.00	199.60	1	199.60			5.43	0.04	43.35			
	3rd Cross Road											
	0.00	114.60	1	114.60			5.73	0.04	26.24			
	4th Cross Road											
	0.00	173.30	1	173.30			5.54	0.04	38.42			
	5th Cross Road											
	0.00	130.00	1	130.00			5.81	0.04	30.22			
	2nd B Cross Road											
	0.00	87.60	1	87.60			4.89	0.04	17.15			
	1st Main Road Beside BBMP Park											
	0.00	279.50	1	279.50			6.17	0.04	68.98			
	2nd Main Road											
	0.00	298.50	1	298.50			5.70	0.04	68.08			
	8th Cross Road											

BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
	0											
	16th Main Road											
			1	0.20			0.30	0.05	0.003			
			1	0.70			4.40	0.05	0.15			
			1	0.20			4.60	0.05	0.05			
	Edge Lines											
	LHS											
			1	15.00			0.40	0.05	0.30			
			1	14.20			0.40	0.05	0.28			
			1	15.00			0.35	0.05	0.26			
			1	15.00			0.35	0.05	0.26			
			1	15.00			0.55	0.05	0.41			
			1	15.00			0.55	0.05	0.41			
			1	15.00			0.85	0.05	0.64			
			1	15.00			0.85	0.05	0.64			
	RHS											
			1	15.00			0.45	0.05	0.34			
			1	14.20			0.45	0.05	0.32			
			1	15.00			0.40	0.05	0.30			
			1	15.00			0.40	0.05	0.30			
			1	15.00			0.40	0.05	0.30			
			1	16.20			0.40	0.05	0.32			
			1	15.00			0.35	0.05	0.26			
			1	15.00			0.35	0.05	0.26			
			1	6.80			0.35	0.05	0.12			
			1	15.00			0.40	0.05	0.30			
			1	8.20			0.40	0.05	0.16			
			1	15.00			0.30	0.05	0.23			
	17th Main Road											
			1	1.00			0.80	0.05	0.04			
			1	0.30			3.40	0.05	0.05			
			1	2.90			0.40	0.05	0.06			
			1	0.30			3.60	0.05	0.05			
			1	0.40			0.40	0.05	0.01			
			1	0.20			5.20	0.05	0.05			
			1	0.30			3.80	0.05	0.06			
			1	1.20			0.30	0.05	0.02			
	Edge Lines											
	LHS											
			1	13.10			0.65	0.05	0.43			
			1	15.00			0.60	0.05	0.45			
			1	15.00			0.60	0.05	0.45			
			1	9.70			0.60	0.05	0.29			
			1	15.00			0.60	0.05	0.45			
			1	15.00			0.60	0.05	0.45			
			1	15.00			0.60	0.05	0.45			
			1	4.80			0.60	0.05	0.14			
	RHS											
			1	15.00			0.25	0.05	0.19			
			1	4.00			0.25	0.05	0.05			
			1	13.40			0.40	0.05	0.27			
			1	3.20			0.30	0.05	0.05			
			1	15.00			0.25	0.05	0.19			
			1	11.80			0.25	0.05	0.15			
			1	15.00			0.45	0.05	0.34			
			1	15.00			0.45	0.05	0.34			
	18th Main Road											
			1	0.80			0.90	0.05	0.04			
			1	5.10			0.50	0.05	0.13			
			1	5.20			0.50	0.05	0.13			
			1	2.60			2.10	0.05	0.27			
	Edge Lines											
	LHS											
			1	10.80			0.90	0.05	0.49			
			1	15.00			0.55	0.05	0.41			
			1	15.00			0.55	0.05	0.41			
			1	10.00			0.55	0.05	0.28			
	RHS											
			1	15.00			1.05	0.05	0.79			
			1	15.00			1.05	0.05	0.79			
			1	9.90			1.05	0.05	0.52			

[illegible]

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	0.00	86.00		1	86.00			6.29	0.04	21.63			
	8th A Cross Road												
	0.00	38.20		1	38.20			5.56	0.04	8.50			
	1st Cross rd (2nd Main Rd)												
	0.00	48.70		1	48.70			4.68	0.04	9.11			
	3rd Cross rd (2nd Main Rd)												
	0.00	120.00		1	120.00			5.74	0.04	27.54			
	4th Cross rd (2nd Main Rd- 1st Main rd)												
	0.00	109.30		1	109.30			5.75	0.04	25.13			
	5th Cross rd (2nd Main Rd- 1st Main rd)												
	0.00	104.30		1	104.30			6.03	0.04	25.16			
	5th Cross rd in Cross Rd 1												
	0.00	25.00		1	25.00			4.25	0.04	4.25			
	5th Cross rd in Cross Rd 2												
	0.00	55.00		1	55.00			6.81	0.04	14.98			
	6th Cross rd (2nd Main Rd)												
	0.00	39.80		1	39.80			4.31	0.04	6.86			
	7th Cross rd (2nd Main Rd)												
	0.00	40.30		1	40.30			5.58	0.04	8.99			
	1st Cross rd Maruthi Farm												
	0.00	25.90		1	25.90			4.25	0.04	4.40			
	2nd Cross rd Maruthi Farm												
	0.00	32.50		1	32.50			4.80	0.04	6.24			
	3rd Cross rd Maruthi Farm												
	0.00	38.50		1	38.50			4.22	0.04	6.50			
	4th Cross rd Maruthi Farm												
	0.00	44.30		1	44.30			4.49	0.04	7.96			
	Muniramayya Layout												
	0.00	48.00		1	48.00			3.26	0.04	6.26			
	5th A cross Road												
	0.00	62.70		1	62.70			5.30	0.04	13.29			
	7th cross Road 1st Main rd												
	0.00	60.50		1	60.50			6.23	0.04	15.07			
	7th A cross Road 1st Main rd												
	0.00	34.70		1	34.70			5.82	0.04	8.08			
	6th cross Road 1st Main rd												
	0.00	83.20		1	83.20			5.62	0.04	18.70			
	1st cross Road C Sector												
	0.00	52.90		1	52.90			6.30	0.04	13.32			
	Talakaveri Layout												
	5th Cross Road												
	0.00	120.00		1	120.00			8.54	0.04	40.99			
	6th Cross Road												
	0.00	191.00		1	191.00			7.97	0.04	60.91			
	6th A Cross Road												
	0.00	138.20		1	138.20			6.40	0.04	35.37			
	7th A Cross Road												
	0.00	149.60		1	149.60			8.62	0.04	51.59			
	7th Cross Road												
	0.00	222.10		1	222.10			7.34	0.04	65.21			
	2nd A Main Road												
	0.00	90.10		1	90.10			6.23	0.04	22.47			
	3rd Main Road												
	0.00	270.00		1	270.00			7.95	0.04	85.81			
	Coffe Board Layout												
	5th Cross Road												
	0.00	179.00		1	179.00			5.07	0.04	36.32			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	Kempapura Main Road												
	0.00	146.00		1	144.80			5.28	0.04	30.58			
	146.00	700.00		1	554.00			9.70	0.04	214.95			
	Vidyanikethan School Road												
	0.00	42.00		1	42.00			7.50	0.04	12.60			
	Sindhi College Gate												
	0.00	277.00		1	277.00			5.20	0.04	57.62			
	Venkatappa Badavane 1st c/s Rd												
	0.00	70.80		1	70.80			3.50	0.04	9.91			
	Connected to 1st c/s Venkatappa Badavane												
	0.00	36.70		1	36.70			3.80	0.04	5.58			
	Venkatappa Badavane 2nd c/s Rd												
	0.00	73.00		1	73.00			3.30	0.04	9.64			
	Venkatappa Badavane 3rd c/s Rd												
	0.00	45.00		1	45.00			3.40	0.04	6.12			
	Heera Cateres Rd (Mariyappanapalya)												
	0.00	79.00		1	79.00			6.40	0.04	20.22			
	MLA CB Krishne Byeregowda House Rd												
	0.00	286.00		1	282.90			7.80	0.04	88.26			
	From Shanthivana Rd end at Sardar Vallabhbbhai Patel												
	0.00	401.50		1	401.50			9.10	0.04	146.15			
	Connecting Rd from Shanthivana Rd to CB Krishna Byeregowda												
	0.00	130.20		1	127.20			9.00	0.04	45.79			
								Total Quantity		5153.59			
								BOQ		4632.08			
								Upto 125%		5153.59	Cum	8686.84	44768427.36
31	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregates , with superplastisiser @3lts conforming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) ((P.No.177, I.No.22.6.1 of PW,P&I WTD SR 2016-17)												
	CC Road												
	Kashinagar cross Roads and Surrounding Area												
				1	115.00			5.00	0.15	86.25			
								Total Quantity		86.25	Cum	6653.22	573840.23
32	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(P.No.177, I.No.22.7 of PW, P&I WTD SR 2016-17)												
	CC Road												
	Kashinagar cross Roads and												
				1	115.00			5.00		575.00			

[illegible]

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage										Rs.	Rs.
	Edge Line		2.00	32.00			0.10		6.40			
	7th Cross Road											
	Edge Line		2.00	64.30			0.10		12.86			
	jakkur Double Rd											
	13th A Cross Road											
	Edge Line		2.00	84.00			0.10		16.80			
	14th A Cross Road											
	Edge Line		2.00	68.00			0.10		13.60			
	15th A Cross Road											
	Edge Line	L/S	1.00	67.00			0.10		6.70			
		L/S	1.00	98.50			0.10		9.85			
		R/S	1.00	218.50			0.10		21.85			
	Center Line		0.50	150.50			0.10		7.53			
	Hoysala samruddhi Appartments Road Opposite to 15th Cross A Road											
	Edge Line		2	47.30			0.10		9.46			
	Talakaveri Badavane 8th Cross Road											
	Edge Line	L/S	1	144.70			0.10		14.47			
		R/S	1	104.70			0.10		10.47			
	Center Line		0.50	104.70			0.10		5.24			
	16th A Cross Road											
	Edge Line	L/S	1	87.00			0.10		8.70			
		R/S	1	76.50			0.10		7.65			
	17th A Cross Road											
	Edge Line		2	27.50			0.10		5.50			
	18th A Cross Road											
	Edge Line		2	46.00			0.10		9.20			
	Approach Road								0.00			
	Edge Line		2	100.50			0.10		20.10			
	19th Cross Road											
	Edge Line		2	177.90			0.10		35.58			
	Approach Road											
	Edge Line		2	52.30			0.10		10.46			
	Kuvempu rd											
	Kuvempu Road Coffe Board Layout (Road)											
	Edge Line		2	256.00			0.10		51.20			
	Center Line		0.50	256.00			0.10		12.80			
	Gopalappa to Cof Board											
	Road Work											
	St Antony Chaurch Road											
	(From Coffe Board Layout Park End)											
	Edge Line		2.00	587.50			0.10		117.5			
	Center Line		0.50	587.50			0.10		29.375			
	Cross Road St Antony Charch Road											
	Edge Line		2.00	143.50			0.10		28.7			
	Center Line		0.50	143.50			0.10		7.175			
	Mandi Mariyappa Rd											
	Road Work											
	7th Cross Road (Mandi Mariyappa Palya)											
	Edge Line		2.00	27.00			0.10		5.40			
	Center Line		0.50	27.00			0.10		1.35			
	3rd Main Road Mariyappa Reddy											
	Edge Line		2.00	772.50			0.10		154.50			
	Center Line		0.50	130.00			0.10		6.50			
			0.50	418.50			0.10		20.93			
	3rd Main Road Mariyanna Palya Continue From (Himagiri Complex)- Road											
	Edge Line		2.00	225.00			0.10		45.00			
	Center Line		0.50	100.00			0.10		5.00			
	Road Work											
	Jain School Road											
	Edge Line		2	38.10			0.10		7.62			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	Center Line			0.50	38.10			0.10		1.91			
	Kempapura Main Road												
	Edge Line			2	698.80			0.10		139.76			
	Center Line			0.50	698.80			0.10		34.94			
	Vidyanikethan School Road												
	Edge Line			2	42.00			0.10		8.40			
	Center Line			0.50	42.00			0.10		2.10			
	Sindhi College Gate												
	Edge Line			2	277.00			0.10		55.40			
	Center Line			0.50	277.00			0.10		13.85			
	Venkatappa Badavane 1st c/s Rd												
	Edge Line			2	36.70			0.10		7.34			
	Center Line			0.50	36.70			0.10		1.84			
	Connected to 1st c/s Venkatappa Badavane												
	Edge Line			2	36.70			0.10		7.34			
	Center Line			0.50	36.70			0.10		1.84			
	Venkatappa Badavane 2nd c/s Rd												
	Edge Line			2	73.00			0.10		14.60			
	Center Line			0.50	73.00			0.10		3.65			
	Venkatappa Badavane 3rd c/s Rd												
	Edge Line			2	45.00			0.10		9.00			
	Center Line			0.50	45.00			0.10		2.25			
	Heera Cateres Rd (Mariyappanapalya)												
	Edge Line			2	79.00			0.10		15.80			
	Center Line			0.50	79.00			0.10		3.95			
	MLA CB Krishne Byeregowda House Rd												
	Edge Line			2	279.80			0.10		55.96			
	Center Line			0.50	279.80			0.10		13.99			
	From Shanthivana Rd end at Sardar Vallabhbhai Patel												
	Edge Line			2	398.40			0.10		79.68			
	Center Line			0.50	398.40			0.10		19.92			
	Connecting Rd from Shanthivana Rd to CB Krishna Byeregowda												
	Edge Line			2	127.20			0.10		25.44			
	Center Line			0.50	127.20			0.10		6.36			

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
38	KSRRB M2100-13. Plain / Reinforced Cement Concrete M15 with OPC cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.84cum and fine aggregates @ 0.56cum in Open Foundation complete as per Drawing and Technical Specifications MORTH Specification No. 1500,1700 & 2100.(P.No.211, I.No.27.24 of PW,P&IWD S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	6784.53	0.00
39	Diversion of water course by providing Coffor dams or bunds or islands as may be necessary for piers and abutments foundations, bailing out or pumping water during excavation and until completion etc., complete.(1.50 mtrs depth below LWL)(P.No.257, I.No.37.41.1 of PW,P&IWD S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	309.7	0.00
40	Diversion of water course by providing Coffor dams or bunds or islands as may be necessary for piers and abutments foundations, bailing out or pumping water during excavation and until completion etc., complete.(beyond 1.50 mtrs depth upto & including 3m)(P.No.257, I.No.37.41.2 of PW,P&IWD S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	381.35	0.00
41	KSRRB M800-43. Installation of a steel portable barricade with horizontal rail 300 mm wide, 2.5 m in length fitted on a 'A' frame made with 45 x 45 x 5 mm angle iron section, 1.5 m in height, horizontal rail painted (2 coats) with yellow and white stripes, 150 mm in width at an angle of 45°, 'A' frame painted with 2 coats of yellow paint, complete as per IRC:SP:55-2001 complete as per specifications.(P.No.186, Item no 24.44 of PW,P&IWD S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Each	2741.08	0.00
42	KSRRB M2100-20.2. Plain / Reinforced Cement Concrete in Open Foundation with OPC cement design mix M35 @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008. case II : With Batching Plant, Transit Mixer and Concrete Pump MORTH Specification No. 1500,1700 & 2100(P.No.213, I.No.27.37 of PW,P&IWD S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	7454.78	0.00
43	KSRRB M2200-5.19. Design mix M35 with OPC cement @ 390kgs,with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 - ii) For height, upto 5m,(P.No.214, I.No.28.7.18 of PW,P&IWD S.R S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	8397.75	0.00
44	KSRRB M2300-8.1. Furnishing and Placing Reinforced/ Prestressed cement concrete in super-structure as per drawing and Technical Specification complete as per specifications. D. RCC / PSC with OPC cement design mix M35 @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, Case - II : Using Batching Plant, Transit Mixer & Concrete Pump MORTH Specification No. 1500,1600 & 1700-Height upto 5 m(P.No.226, I.No.29.16.1 of PW,P&IWD S.R S.R 2016-17)											
	Item of Work Not Operated											
	Total Quantity								0.00	Cum	8048.75	0.00

[illegible]

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
	Chainage											Rs.	Rs.
	0.00	84.00		1	84.00			6.08	0.04	20.43			
	Ramp Asphalt 5*1.2			1	5.00			1.20	0.04	0.24			
	14th A Cross Road												
	0.00	68.00		1	68.00			5.98	0.04	16.27			
	Ramp Asphalt 7.3*2			1	7.30			2.00	0.04	0.58			
	15th A Cross Road												
	0.00	218.50		1	218.50			7.82	0.04	68.36			
	Ramp Asphalt 7.3*2			1	7.30			2.00	0.04	0.58			
	Hoysala samruddhi Appartments Road Opposite to 15th Cross A Road												
	0.00	47.30		1	47.30			5.06	0.04	9.57			
	Talakaveri Badavane 8th Cross Road												
	0.00	144.70		1	144.70			8.03	0.04	46.48			
	16th A Cross Road												
	0.00	125.10		1	125.10			5.56	0.04	27.81			
	17th A Cross Road												
	0.00	27.50		1	27.50			5.79	0.04	6.37			
	Approach			1	1.50			5.00	0.04	0.30			
	18th A Cross Road												
	0.00	46.00		1	46.00			4.68	0.04	8.60			
	Approach Road												
	0.00	100.50		1	100.50			4.96	0.04	19.94			
	Jakkur Double Rd												
	19th Cross Road												
	0.00	177.90		1	177.90			6.56	0.04	46.68			
	Approach Road												
	0.00	52.30		1	52.30			7.21	0.04	15.09			
	19th A Cross Road												
	0.00	138.80		1	138.80			4.56	0.04	25.29			
	4th Bill kuvempu Rd												
	Tack Coat for BC												
	Kuvempu Road Coffe Board Layout (Road)												
	0.00	256.00		1	256.00			7.62	0.04	78.05			
	Gopalappa to Cof Board												
	St Antony Chaurch Road												
	(From Coffe Board Layout Park End)												
	0.00	587.50		1	587.50			7.50	0.04	176.16			
	Cross Road St Antony Charch Road												
	0.00	142.50		1	142.50			6.40	0.04	36.49			
	Mandi Mariyappa Rd												
	7th Cross Road (Mandi Mariyappa Palya)												
	0.00	27.00		1	27.00			3.58	0.04	3.87			
	Road Cut Portion												
	3rd Main Road (Mandi Mariyappa Reddy Road)												
	0.00	772.50		1	772.50			8.00	0.04	247.20			
	3rd Main Road Mariyanna Palya Continue From (Himagiri Complex)- Road												
	0.00	225.00		1	225.00			7.00	0.04	63.00			
	Jain School Road												
	0.00	38.10		1	38.10			6.29	0.04	9.59			

[illegible]

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
82	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required conforming to IEC 60898. 5-32Amps TPN P No. 47 / I No 6.16.5 KPWD SR 2014-15											
	Kempegowda Circle Mazid		1						1.00			
	Mahalakshi Medical, Ambedka		1						1.00			
								Total	2.00	No	1655.29	3,310.58
83	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 49, I. No. 6.40.2 KPWD Electrical SR 2014-15											
	16SWG											
	Kempegowda Circle Mazid		2	115.00		60.00			13800			
			1	295.00		25.00			7375			
	Mahalakshi Medical, Ambedka		2	125.00		60.00			15000			
			1	305.00		25.00			7625			
								Total	43800.00	Sq.Cm	0.35	15,330.00
84	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. 12.5HP to 15 HP Star Delta Starter SERDED Rate											
	Kempegowda Circle Mazid		1						1.00			
	Mahalakshi Medical, Ambedka		1						1.00			
								Total	2.0	No.	11770.00	23,540.00
85	Earthwork excavation for pipeline trenches including deporting or bank up to a lead of 50 mtrs including shirry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following structure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil											
	Kempegowda Circle Mazid		1	25.00		0.60		0.75	11.25			
			1	35.00		0.60		0.75	15.75			
	Mahalakshi Medical, Ambedka		1	28.00		0.60		0.75	12.60			
	5th Cross Road		1	32.00		0.60		0.75	14.40			
								Total	54.00	Cum	201.16	10,862.64
86	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and includng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 Item No.3.4.2 b PRED SR 2012-13.											
	75 mm dia 6 KSC PVC pipe											
	Kempegowda Circle Mazid		1	25.00					25.00			
			1	35.00					35.00			
	Mahalakshi Medical, Ambedka		1	28.00					28.00			
			1	32.00					32.00			
								Total	120.00	Rmtr	167.99	20,158.80
87	Refilling the basement and pipeline treanches with secieted available earthe for trench excavation including authority condition in layers from thedi including dispnsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13											
								Qty. Vide Item No. 85	54.00	Cum	65.27	3,524.58

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No
											Rs.	Rs.	
88	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / I.13.37 PWD SR - 2016-17												94
	Kempegowda Circle Mazid		2						2.00				
	Mahalakshi Medical, Ambedka		2						2.00				
								Total	4.00	Each	2371.29	9,485.16	
	Room For RO Plant												
89	KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications. specification, No. KBS 2.1(a) / 2.3.5, Page No. 5 / Item No. 2.3/ PWD SR 2016-17												
	Columns		4	1.20			1.20	1.20	6.91				
	Foundation												
	Long Wall		2	5.45			0.90	0.80	7.85				
	Short Wall		2	3.00			0.90	0.80	4.32				
	Deduction(-)		-4	0.23			0.23	0.80	-0.17				
								Total Qty	18.91	Cum	218.41	4,130.29	95
90	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2. No. 12/ Item No. 4.3/ PWD SR 2016-17												
	Columns		4	1.20			1.20	0.15	0.86				
	Foundation												
	Long Wall		2	5.45			0.90	0.15	1.47				
	Short Wall		2	3.00			0.90	0.15	0.81				
	Deduction(-)		-4	0.23			0.23	0.15	-0.04				
								Total Qty	3.10	Cum	5,624.31	17,435.36	
91	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.6 / PWD SR 2016-17												
	Foundation												
	Long Wall		2	5.30			0.75	0.60	4.77				
	Short Wall		2	3.15			0.75	0.60	2.83				
	Deduction(-)		-4	0.23			0.23	0.60	-0.13				
								Total Qty	7.47	Cum	4838.50	36,143.60	
92	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5-1.13 Page No. 23 / Item No. 5.9 / PWD SR 2015-16												
	Foundation												
	Long Wall		2	5.00			0.45	0.45	2.02				
	Short Wall		2	3.45			0.45	0.45	1.39				
	Deduction(-)		-4	0.23			0.23	0.45	-0.10				
								Total Qty	3.31	Cum	5783.78	19,144.31	
93	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification No. KBS 2.9 (P.6/2.10) PWD SR 2016-17												
	Qty Vide Item No. 89		1						18.91				
	Qty Vide Item No. 90		-1						-3.10				
	Column Footing		-1						-2.59				
	Column Below Ground Level		-1						-0.25				
								Total Qty	12.97	Cum	146.76	1,903.58	

Modified Estimate													Page 95 of 102	
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount		
	Chainage										Rs.	Rs.		
94	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 5.00 N/mm ² conforming to IS 2185 (Part) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including													
	Wall Portion		2	4.70				2.70	25.38					
			2	3.75				2.70	20.25					
	Parapet Wall		2	4.70				0.40	3.76					
			2	3.75				0.40	3.00					
	Steps		2	4.05				0.20	1.62					
			2	4.05				0.20	1.62					
	Deductions RS		-1	3.00				2.10	-6.30					
	V		-1	1.20				1.20	-1.44					
Total Qty									47.89	Sqm	1082.80	51,855.29		
95	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts conforming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1.4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17													
	Column Footing		4	1.20			1.20	0.45	2.59					
	Column Below Ground Level		4	0.23			0.23	1.20	0.25					
	Plinth Beam		2	4.78			0.23	0.20	0.43					
			2	3.67			0.23	0.20	0.33					
	Column Above Ground Level		4	0.23			0.23	2.70	0.57					
	Lintels		1	3.59			0.20	0.15	0.10					
			1	1.50			0.20	0.15	0.04					
	Roof Beam		2	4.78			0.23	0.30	0.65					
			2	3.67			0.23	0.30	0.50					
	Roof Slab		1	4.70			4.05	0.15	2.85					
	Projection		1	4.05			0.60	0.15	0.36					
	Total Qty									8.67	Cum	6946.31	60,224.51	
	96	KSRB 4.2.10 : Providing and laying in position reinforced cement concrete of mix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplasticiser @ 0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, curing, complete as per specification. Specification NO. KBS 4.1, 4.6 Page No. 14 / Item No. 4.19 / PWD SR 2016-17												
		Chajja		1	1.20			0.20	0.15	0.03				
Total Qty									0.03	Sqm	526.95	15.81		
97	KSRB 4.9.1: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17 / Item No. 4.46.2 / PWD SR 2016-17 - FE 500													
	F1 (1200 X 1200) mm	4												
	16 mm Dia Main Bars	4	10	1.50				1.58	94.81					
	16 mm Column	4	10	1.50				1.58	94.81					
	C (230 X 230) mm	4												
	Main Bars @16mm D	4	4	1.20				1.58	30.34					

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
59	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.) P. 46 / I. 9.1 PRED SR 2012-13 - 100 to 150m											
	100 to 150 m											
	Kempegowda Circle Mazid		1	50.00					50.00			
	Mahalakshi Medical, Ambedka		1	50.00					50.00			
	Total								100.00	Rmtr	476.15	47,615.00
60	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.) P. 46 / I. 9.1 PRED SR 2012-13 - 150 to 200m											
	150 to 200 m											
	Kempegowda Circle Mazid		1	50.00					50.00			
	Total								50.00	Rmtr	502.90	25,145.00
61	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.) P. 46 / I. 9.1 PRED SR 2012-13 - 200 to 250m											
	200 to 250 m											
	Kempegowda Circle Mazid		1	36.00					36.00			
	Total								36.00	Rmtr	582.08	20,954.88
62	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming to IS 554/1985, one end fixed with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and duties) Prices include Collar-medium duty P. iii, I No. 84 PRED SR 2012-13											
	Kempegowda Circle Mazid		1	30.50					30.50			
	Mahalakshi Medical, Ambedka		1	20.00					20.00			
	Total								50.50	Rmtr	1417.75	71,596.38
63	Providing 250mm dia PVC Pipe 6kg/cm SE PRED Approved Rate											
	Kempegowda Circle Mazid		1	24.00					24.00			
	Mahalakshi Medical, Ambedka		1	12.00					12.00			
	Total								36.00	Rmtr	807.28	29,062.08
64	Providing and fixing 160mm Borewell Cap P. iii, I No. 85											
	Kempegowda Circle Mazid		1						1.00			
	Mahalakshi Medical, Ambedka		1						1.00			
	Total								2.00	Each	107.00	214.00
65	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required accessories such as suction, casing suction strainers sand guard Non return valve etc. complete. The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps PWD SR 2016-17 P. XXXII Item No. 24 including of all taxes											
	12.5 HP 25 Stage											
	Kempegowda Circle Mazid		1						1.00			
	Mahalakshi Medical, Ambedka		1						1.00			

Modified Estimate											Page 97 of 102		
BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	
											Rs.	Rs.	
101	KSRB 15.3.11 :Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, ; Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.19 / PWD SR 2016-17 (Inside wall)												
	Inside wall		2	4.40				3.00	26.40				
			2	3.75				3.00	22.50				
	Deductions - For rolling shutte		-1	3.00				2.10	-6.30				
	Window		-1	1.20				1.20	-1.44				
								Total Qty	41.16	Sqm	270.41	11,130.08	
102	KSRB 15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (P. 115 / I. 15.33 PWD SR - 2016-17).												
		Qty Vide Item No. 100+101							57.66				
								57.66	Sqm	28.89	1,665.80		
103	KSRB 15.3.9: Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 114 / Item No. 15.17 / PWD SR 2016-17 (Out side Wall)												
	Out Side		2	4.70				3.00	28.20				
			2	4.07				3.00	24.42				
	Parapet Wall		2	4.70				0.90	8.46				
			2	3.75				0.90	6.75				
	Slab Projection bottom		1	4.05	0.60				2.43				
	deduction for RS		-1	3.00				2.10	-6.30				
	Window		-1	1.20				1.20	-1.44				
								Total Qty	62.52	Sqm	228.81	14,305.20	
104	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications PWD SR 2016-17 (P.117 /I. 15.49.1)												
		Qty Vide Item No.13							57.66				
	Inside wall		2	4.40				1.80	15.84				
			2	3.75				1.80	13.50				
	Deductions - For rolling shutte		-1	3.00				1.80	-5.40				
	Window		-1	1.20				1.20	-1.44				
								Total Qty	80.16	Sqm	82.05	6,577.13	
105	KSRB 15-16.1: providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications PWD SR 2016-17 (P. 118 / I. 15.53.2) with Primer												
		Qty Vide							62.52				
								Total Qty	62.52	Cum	97.07	6,068.82	
106	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 121 / Item No. 15.74 / PWD SR 2016-17												
	Out Side		2	3.60				2.70	19.44				
								Total Qty	19.44	Sqm	94.76	1,842.13	
107	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. Page No. 107 / Item No. 14.43 / PWD SR 2016-17												
	Floor Tiles		1	4.57			3.65		16.68				
			2	4.57				1.20	10.96				
			2	3.65				1.20	8.76				
	For Steps		1	4.07			0.73		2.97				
			2	0.20			0.20		0.08				

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
			1	4.07			0.73		2.97			
			2	0.40			0.40		0.32			
	Deduction RS		-1	3.00				1.20	-3.60			
								Total Qty	39.14	Sqm	1375.16	53,823.76
108	Providing and laying/fixing cement base, precast pre-polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring reads of steps of steps and landin, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of material,s including cutting, griding the edge ti half/ful rounf wherever requires labour, curing complete as per specification Page No. 109 / Item No. 14.62 / PWD SR 2016-17											
	Item of Work Not Operated											
								Total Quantity	0.00	Sqm	1253.83	0.00
109	KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm thick reeded glass with teakwood beading of required size, all steel section should confirm to I.S. 7452:1990, 4nos, of holdfasts of approved size section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be thoroughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification NO. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 Page No. 32 / Item No. 7.7/ PWD SR 2015-16											
			1	1.20				1.20	1.44			
								Total Qty	1.44	Sqm	4079.27	5,874.15
110	KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete Including pulling hooks, 4nos handles wit hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m Specification NO. KBS 7.10 / 7.12 Page No. 31 / Item No. 7.5/ PWD SR 2015-16											
			1	3.00				1.20	3.60			
								Total Qty	3.60	Sqm	3307.33	11,906.39
111	Providing revrsrse osmosis system to cover 2000 Liters of High TDS water per hour with RAW WATER PUMP, SAND MEDIA FILTER, ACTIVATE CARBON FILTER, DOSING SYSTEM, MICRON FILTER, HIGH PRESSURE PUMP, RO membrane housing, RO MEMBRANES, RO CLEANSING SYSTEM, ELECTRICAL PANEL, INSTRUMENTATION, PH DOSING SYSTEM											
	Item of Work Not Operated											
								Total Quantity	0.00	No's	551050	0.00
	ELECTRIFICATION											
112	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A (Page No. 05, Item No.2.1 KPWD SR 2014-15. b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch											
			2						2	Point	262.15	524.30

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount
											Rs.	Rs.
113	c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch											
			2						2.00	Point	388.40	776.80
114	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting. Finishing with necessary cement plastering complete (Page No. 03, Item No. 1.6) KPWD SR 2014-15, (1.6.5) 4"x4"x3" (101x101x76mm)											
			12						12	Each	72.76	873.12
115	(1.6.1) 12"x12"x3" (300x300x76mm)											
			6						6	Each	124.12	744.72
116	(1.6.3) 10"x7"x3" (254x178x76mm)											
			6						6	Each	93.09	558.54
117	Supplying 4mm thick plastic sheet with necessary niches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws. (Page No. 17, Item No. 3.9) KPWD SR 2014-15											
			6660						6600	SqCM	0.27	1,782.00
118	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall (Page No. 03, Item No. 1.7.1) KPWD SR 2014-15											
			10						10.00	Mtr	22.5	224.70
119	Supplying heavy gauge PVC Conduit Pipe 19/20 mm dia 2 mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. (Page No. 02, Item No. 1.3.1) KPWD SR 2014-15											
			10						10.00	Mtr	59.9	599.20
120	Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps. (Page No. 20, Item No. 4.2) KPWD SR 2014-15											
			2						2.00	Each	94.2	188.32
121	Supplying patti type fluorescent tube light fitting of 2' - suitable for 14 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with HF Electronic Ballast, locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC. Supply including T5 lamp. (Page No. 20, Item No. 4.5) KPWD SR 2014-15											
			2						2.00	Each	632.4	1,264.74
122	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & conforming to GTP of GROUP -A 1.5 sqmm (Page No. 06, Item No. 2.5.2) KPWD SR 2014-15											
			5						5.00	Mtr	19.9	99.50
123	Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 60/100 watts 230V GLS lamp. (Page No. 20, Item No. 4.3) KPWD SR 2014-15											
			4						4.00	Each	799.3	3,197.16

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
	Distribution Bars @ 150	4	6	0.90				0.40	8.53			
	Plinth Beam											
	PB1	2										
	12 mm dia	2	2	4.45				0.89	15.82			
	16 mm dia	2	2	4.45				1.58	28.13			
	Distribution Bars @ 150	2	22	0.90				0.40	15.64			
	PB2	2										
	12 mm dia	2	2	5.08				0.89	18.06			
	16 mm dia	2	2	5.08				1.58	32.11			
	Distribution Bars @ 150	2	25	0.90				0.40	17.78			
	Column Above Plinth Beam											
	C (230 X 230)mm	4										
	Main Bars @16mm D	4	4	2.70				1.58	68.27			
	Distribution Bars @ 150	4	14	0.90				0.40	19.91			
	Roof Beam											
	RB1	2										
	12 mm dia	2	2	4.45				0.89	15.82			
	16 mm dia	2	2	4.45				1.58	28.13			
	Distribution Bars @ 150	2	22	0.90				0.40	15.64			
	RB2	2										
	12 mm dia	2	2	5.08				0.89	18.06			
	16 mm dia	2	2	5.08				1.58	32.11			
	Distribution Bars @ 150	2	25	0.90				0.40	17.78			
	Slab Including Projection											
	Main Bars 10mm @150	1	37	4.37				0.62	99.81			
	Distribution Bars 8mm	1	29	5.60				0.40	64.16			
	Chajja											
	Main Bars 8mm @150	1	8	0.20				0.40	0.63			
	Distribution Bars 8mm	1	1	1.20				0.40	0.47			
									736.85			
	Total Qty							0.737		Ton	80337.31	59,196.20
98	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.31/ PWD SR 2016-17											
	Column Below Ground Level	4	0.92					1.20	4.41			
	Plinth	2	16.90					0.20	6.76			
	Column Above Ground Level	4	0.92					2.70	9.93			
	Lintels	2	3.59					0.15	1.07			
		2	1.50					0.15	0.45			
	Roof Beam	2	16.90					0.30	10.14			
	Roof	1	4.70	4.05					19.03			
	Projection	1	4.05	0.60					2.43			
	Sides	2	4.70					0.15	1.41			
		2	4.05					0.15	1.21			
									56.84			
99	KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16 / Item No. 4.37 / PWD SR 2016-17											
		1	4.50				0.60		2.70			
	Total Qty							2.70		Sqm	312.01	842.43
100	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.21 / PWD SR -2016-17											
	Ceiling Plastering	1	4.40				3.75		16.50			
	Total Qty							16.50		Sqm	223.03	3,680.00

BOQ Item No	Description Chainage	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate Rs.	Amount Rs.
130	Thiristor based single/ Three phase smart street light control and monitoring system Remotely control and and monitorable smart street light system by using web or mobile application .smart control system has hardware ruggedness over field issues like line cross, line short, lighting and any other irregularities in voltage. It has some features like 1.Remote lighting management 2.Precise lighting turnoff.3.Load ballancing.4.Load power regulation.5.Status tracking. It works on the basis of some of these features 1) Main Control Unit (Mother board) : Handles controlling , data handling and other communication process. 2) Communication unit: GSM/GPRS quad bandwith RS232 interface wireless communication unit 3) Gate Driver Unit: Firing angle controllable board for driving the thyristor 4) Switching Thyristor: SCR 110 AMPS dual thyristor modules for switching		30.00						30.00	Each		
	Total Qty								30.00	Each	55105.00	1653150.00
131	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes25 sqmm Long Barrel		72.00						72.00			
	Total Qty								72.00	Each	22.03	1586.16
E1	KSRRB 300-6. Excavation in soft rock / ordinary rock without blastingfor formation of roads including stacking neatly, to uniform line and level withan initial lead upto 15m. including cost of all labour, equipments, completeas per specifications.(Pg.No. 143, I.No.19.6 of PW, P&IWTD SR 2018 - 19)											
	UGD Cut Portion for NP3 Pipe installations											
	Jain School Road											
	0.00 38.10		1	38.10			0.60	0.50	11.43			
	Kempapura Main Road											
	0.00 558.80		1	558.80			0.60	0.50	167.64			
	Deduct Manhole Volume		-26	1.20			0.60	0.50	-9.36			
	Total Quantity								169.71	Cum	1,541.89	2,61,674.15
E2	Providing and laying reinforced cement concrete pipe NP3 of 450mm dia for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour curing complete as per specifications. Specification No.KSRB 1000, 2300 MOST Specification No. 1000 / 2300 (Pg.No. 255, I.No. 34.6.5 of PW, P&IWTD SR 2018 - 19)											
	UGD Cut Portion for NP3 Pipe installations											
	Jain School Road											
	0.00 38.10		1	38.10					38.10			
	Kempapura Main Road											
	0.00 558.80		1	558.80					558.80			
	Deduct Manhole Volume		-26.00	1.00					-26.00			
	Total Quantity								570.90	Rmtr	3,281.20	18,73,237.08
E3	KSRRB 2.6:Providing and filling Stone Dust in trenches to required depth including watering ramming with all leads and lift. complete as per specification and as directed by Engineer-in-charge (P.No.7, I.No.2.13 of PW,P&IWTD SR 2018-19)											
	UGD Cut Portion for NP3 Pipe installations											
	Jain School Road											
	0.00 38.10		1	38.10			0.60	1.00	22.86			
	Kempapura Main Road											
	0.00 558.80		1	558.80			0.60	1.00	335.28			
	Deduct Manhole Volume		-26	1.20			0.60	1.00	-18.72			
	Total Quantity								339.42	Cum	1,578.81	5,35,879.69

BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount	BOQ Item No	
	Chainage										Rs.	Rs.		
124	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia (Page No. 55, Item No. 7.1) KPWD SR 2014-15		1						1.00	No	2917.9	2,917.89	130	
125	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS, UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w at 1W/ & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 5 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED source manufacture. Suitable for B1/B2 Roads as per IS 1944 Part I & Part II. LED Streetlight 65watts												131	
	Street Lights		117						117.00					E1
									Total Qty	117.00	Each	20030.40	2343556.80	
126	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. Using 32mm dia G.I. pipe													E2
	Class A GI Pipe		182						182.00					
									Total Qty	182.00	Each	955.51	173902.82	
127	Wiring for lighting/power circuit using one of PVC insulated 1100v grade stranded Aluminium unsheathed wire single core/multi core cable in open or concealed system of wiring. a)4 sqmm.		1.00	600.0					600.00					
									Total Qty	600.00	Each	8.03	4818.00	
128	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) conforming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & conforming to GTP of GROUP-A.3.5 core 25		1.00	200.0					200.00	Per Mtr				E3
									Total Qty	200.00	Each	177.19	35438.00	
129	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct.25 sqmm to 75 sqmm		1.00	200.0					200.00					
									Total Qty	200.00	Each	37.24	7448.00	

Modified Estimate													Page 102 of 1	
BOQ Item No	Description	Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit	Rate	Amount		
	Chainage										Rs.	Rs.		
E4	KSRB 4-1.4 : Providing and laying in position plain cement concrete of Mix 1:5:10 with OPC @ 160kgs, with 40mm and down size graded granite metal coarse aggregates @0.86cum and fine aggregates @ 0.58cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2													
	CC Road													
	Kashinagar cross Roads and Surrounding Area													
			1	115.00			5.00	0.15	86.25					
							Total Quantity		86.25	Cum	6,370.57	5,49,461.66		
											Total	9,85,98,995.50		
											Cost towards Preparation of DPR and PMC / Third Party inspection LS	15,00,000.00		
											Sub Total	10,00,98,995.50		
											Miscellaneous and rounding off	1,004.50		
											Total	10,01,00,000.00		

Certificate.

- 1 The rates adopted based on the PWD SR, Bangalore circle for year 2016-17, 2018-19.
- 2 The provisions made in the estimate are necessary and essential.
- 3 The workspot was inspected and work is found to be necessary.
- 4 The area comes within the Bruhat Bangalore Mahanagara Palike limits.



M. H. N. D.
Assistant Engineer

C. P. D.
Assistant Executive Engineer

M. Chandra
Executive Engineer

Technical Sanction
Accorded For Rs. 10,01,00,000.00
Head of A/C P. 3.1.58
CER NO : 95 Dt. 27-04-2022

ಯಲಹಂಕ ವಲಯ
ಬಿಹೆಚ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ